



September 22, 2000

State of Utah DOGM
1594 West North Temple, Suite #1210
P.O. Box 145801
Salt Lake City, Utah 84114-5801

Attention: Lisha Cordova

Enclosed is the original and one copy (each) of the Application for Permit to Drill for the locations listed below:

✓NBU #361 NBU #345 ✓NBU #358
✓NBU #367 ✓NBU #359 ✓NBU #347

Please contact me as soon as possible in order to schedule an on-site.

If you have any questions or need additional information, please do not hesitate to call me, (435)-781-7023.

Sincerely,

Cheryl Cameron
Sr. Regulatory Analyst

CC: SU/WF

RECEIVED
SEP 27 2000
BUREAU OF
OIL, GAS & MINING

Coastal Oil & Gas Corporation

A SUBSIDIARY OF THE COASTAL CORPORATION

1368 S 1200 E • P.O. BOX 1148 • VERNAL UT 84078 • 435/789-4433 • FAX 435/789-4436

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

APPLICATION FOR PERMIT TO DRILL OR DEEPEN

1A. Type of Work

DRILL ☒DEEPEN ☐

B. Type of Well

OIL ☐GAS ☒

OTHER:

SINGLE ZONE ☐MULTIPLE ZONE ☐

2. Name of Operator:

Coastal Oil & Gas Corporation

3. Address and Telephone Number:

P.O. Box 1148, Vernal UT 84078

(435)-781-7023

4. Location of Well (Footages)

At surface: NW NE

At proposed proding zone:

1220' FNL & 2035' FEL

14. Distance in miles and direction from nearest town or post office:

19.6 Miles from Ouray, Utah

15. Distance to nearest property or lease line (feet):

1220'

16. Number of acres in lease:

640

17. Number of acres assigned to this well:

N/A

18. Distance to nearest well, drilling, completed, or applied for, on this lease (feet):

Refer to Topo "C"

19. Proposed Depth:

10100'

20. Rotary or cable tools:

Rotary

21. Elevations (show whether DR, RT, GR, etc.):

5196.2' Ungraded GR

22. Approximate date work will start:

Upon Approval

23.

PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	GRADE, SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
11"	8 5/8" J-55	32#	2500'	620 sx
7 7/8"	4 1/2" P-110	11.6#	10100'	2400 sx

DESCRIBE PROPOSED PROGRAM: If proposal is to deepen, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

Coastal Oil & Gas Corporation is considered to be the operator of the subject well. Coastal Oil & Gas Corporation agrees to be responsible under terms and conditions of the lease for the operations conducted upon leased lands.

Bond coverage pursuant to 43 CFR 3104 for lease activities being provided by Coastal Oil & Gas Corporation Bond #102103, and BLM Nationwide Bond #U-605382-9.

24.

Name & Signature

Cheryl Cameron

Title: Sr. Regulatory Analyst

Date: 9/14/00

(This space for State use only)

API Number Assigned:

43-047-33706

Approval:

**Approved by the
Utah Division of
Oil, Gas and Mining**

Date:

By:

(See Instructions on Reverse Side)

RECEIVED

SEP 25 2000

DIVISION OF
OIL, GAS AND MINING



T10S, R21E, S.L.B.&M.

COASTAL OIL & GAS CORP.

Well location, NBU #359, located as shown in the NW 1/4 NE 1/4 of Section 29, T10S, R21E, S.L.B.&M., Uintah County, Utah.

BASIS OF ELEVATION

TWO WATER TRIANGULATION STATION LOCATED IN THE NW 1/4 OF SECTION 1, T10S, R21E, S.L.B.&M. TAKEN FROM THE BIG PACK MTN NE QUADRANGLE, UTAH, UTAH COUNTY, 7.5 MINUTE SERIES (TOPOGRAPHICAL MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5238 FEET.



CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE SURVEY WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

REGISTERED LAND SURVEYOR
 REGISTRATION NO. 161319
 STATE OF UTAH

LEGEND:

- └─┘ = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.

LATITUDE = 39°55'21"
 LONGITUDE = 109°34'22"

UINTAH ENGINEERING & LAND SURVEYING

85 SOUTH 200 EAST - VERNAL, UTAH 84078

(435) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 07-03-00	DATE DRAWN: 08-03-00
PARTY K.K. P.R. D.R.B.	REFERENCES G.L.O. PLAT	
WEATHER WARM	FILE COASTAL OIL & GAS CORP.	

COASTAL OIL & GAS CORP.

NBU #359

LOCATED IN UINTAH COUNTY, UTAH
SECTION 29, T10S, R21E, S.L.B.&M.



PHOTO: VIEW FROM CORNER #5 TO LOCATION STAKE

CAMERA ANGLE: NORTHEASTERLY



PHOTO: VIEW FROM BEGINNING OF PROPOSED ACCESS

CAMERA ANGLE: NORTHERLY



Uintah Engineering & Land Surveying

85 South 200 East Vernal, Utah 84078
435-789-1017 uels@uelsinc.com

LOCATION PHOTOS

8 17 00
MONTH DAY YEAR

PHOTO

TAKEN BY: K.K.

DRAWN BY: C.G.

REVISED: 00-00-00

NBU #359
NW/NE Sec. 29, T10S-R21E
Uintah County, UT
ML-21330

ONSHORE ORDER NO. 1
COASTAL OIL & GAS CORPORATION

DRILLING PROGRAM

1. **Estimated Tops of Important Geologic Markers:**

<u>Formation</u>	<u>Depth</u>
KB	5275'
Green River	1190'
Wasatch	4270'
Mesaverde	7138'
L. Mesaverde A	9506'
Total Depth	9600'

2. **Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations:**

<u>Substance</u>	<u>Formation</u>	<u>Depth</u>
	Green River	1190'
Gas	Wasatch	4270'
Gas	Mesaverde	7138'
	L. Mesaverde A	9506'
Water	N/A	
Other Minerals	N/A	

3. **Pressure Control Equipment** (Schematic Attached)

The BOP stack will consist of one 11" 3,000 psi annular BOP, one 11" 3,000 psi double ram, and one 11' drilling spool. The lower ram will contain pipe rams, and the upper ram will contain blind rams.

The choke and kill lines and the choke manifold will have a 3,000 psi minimum pressure rating.

The hydrill will be tested to 1,500 psi. The rams, choke manifold, kelly safety valves, drill string safety valves, and inside BOP will be tested to 2,000 psi.

4. **Proposed Casing & Cementing Program:**

Refer to the attached Cement & Casing Program

RECEIVED

SEP 25 2000

DIVISION OF
OIL, GAS AND MINING

5. **Drilling Fluids Program:**

<u>Depth</u>	<u>Type</u>	<u>Mud Wt.</u>
0-2500'	Air/Mist	N/A
SC-TD	Mist/Water/Mud	8.5-11.0

6. **Evaluation Program:** (Logging)

<u>Depth</u>	<u>Log Type</u>
SC-TD	Platform Express with Sonic

7. **Abnormal Conditions:**

Maximum anticipated bottomhole pressure calculated @ 9600' TD approximately equals 3,840 psi (calculated at 0.4 psi/foot).

Maximum anticipated surface pressure equals approximately 1,728 psi (bottomhole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot).

RECEIVED

SEP 25 2000

DIVISION OF
OIL, GAS AND MINING

NBU #359
NW/NE Sec. 29, T10S-R21E
Uintah County, UT
ML-21330

ONSHORE ORDER NO. 1

MULTI-POINT SURFACE USE & OPERATIONS PLAN

1. Existing Roads:

Refer to Topo Map A for directions to the location.

Refer to Topo Maps A and B for location of access roads within a 2-mile radius.

To reach the NBU #359 location proceed in a westerly direction from Vernal, Utah along U.S. highway 40 approximately 14.0 miles to the junction of state highway 88; exit left and proceed in a southerly direction approximately 17.0 miles on state highway 88 to Ouray, Utah; proceed in a southerly direction from Ouray approximately 15.1 miles to the Seep Ridge road to the junction of this road and an existing road to the east; turn left and proceed in an easterly direction approximately 1.2 miles to the junction of this road and an existing road to the north; turn left and proceed in a northerly then northeasterly direction approximately 1.6 miles to the beginning of the proposed access to the north; follow road flags in a northerly direction approximately 0.3 miles to the proposed access.

Total distance from Vernal, Utah to the proposed well location is approximately 49.2 miles.

Refer to Topo Maps A and B for location of access roads within a 2 mile radius.

Improvements to existing access roads shall be determined at the on-site inspection.

All existing roads will be maintained and kept in good repair during all drilling and completion operations associated with this well.

2. Planned Access Roads:

Refer to Topo Map B for the location of the proposed access road.

The upgraded and new portions of the access road will be crowned and ditched with a running surface of 18 feet and a maximum disturbed width of 30 feet, ***unless modified at the on-site inspection.*** Appropriate water control will be installed to control erosion.

Existence of pipelines; maximum grade; turnouts; major cut and fills, culverts, or bridges; gates, cattle guards, fence cuts, or modifications to existing facilities shall be determined at the on-site.

The access road was centerline flagged during time of staking.

Surfacing material may be necessary, depending upon weather conditions.

RECEIVED

SEP 25 2000

**DIVISION OF
OIL, GAS AND MINING**

Surface disturbance and vehicular traffic will be limited to the approved location and approved access route. Any additional area needed will be approved in advance.

3. **Location of Existing Wells Within a 1-Mile Radius:**

Please refer to Topo Map C.

4. **Location of Existing & Proposed Facilities:**

The following guidelines will apply if the well is productive.

All production facilities will be located on the disturbed portion of the well pad and at a minimum of 25 feet from the toe of the back slope or the top of the fill slope.

A dike will be constructed completely around those production facilities which contain fluids (i.e., production tanks, produced water tanks, and/or heater/treater). These dikes will be constructed of compacted subsoil, be impervious, hold 100% of the capacity of the largest tank, and be independent of the back cut.

All permanent (on-site six months or longer) above the ground structures constructed or installed, including pumping units, will be painted a flat, non-reflective, earthtone color to match one of the standard environmental colors, as determined by the five state Rocky Mountain Inter-Agency Committee.

All facilities will be painted within six months of installation. Facilities required to comply with the Occupational Safety and Health Act (OSHA) will be excluded. The required color is Desert Brown, Munsell standard color number 10 YR 6/3.

Any necessary pits will be properly fenced to protect livestock and prevent wildlife entry.

Refer to Topo D for the proposed pipeline.

5. **Location and Type of Water Supply:**

Water for drilling purposes will be obtained from Dalbo Inc.'s underground well located in Ouray, Utah, Sec. 32, T4S, R3E, Water User Claim #43-8496, Application #53617.

Water will be hauled to location over the roads marked on Maps A and B.

No water well is to be drilled on this lease.

6. **Source of Construction Materials:**

Surface and subsoil materials in the immediate area will be utilized.

Any gravel will be obtained from a commercial source.

7. **Methods of Handling Waste Materials:**

Drill cuttings will be contained and buried in the reserve pit.

RECEIVED

SEP 25 2000

DIVISION OF
OIL, GAS AND MINING

Drilling fluids, including salts and chemicals, will be contained in the reserve pit. Upon termination of drilling and completion operations, the liquid contents of the reserve pit will be removed and disposed of at an approved waste disposal facility within 120 days after drilling is terminated.

The reserve pit will be constructed on the location and will not be located within natural drainage, where a flood hazard exists or surface runoff will destroy or damage the pit walls. The reserve pit will be constructed so that it will not leak, break, or allow discharge of liquids. *The need for a reserve pit liner will be determined at the on-site inspection.*

If a plastic reinforced liner is used, it will be a minimum of 12 mil thick, with sufficient bedding used to cover any rocks. The liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place. No trash or scrap that could puncture the liner will be disposed of in the pit.

Any spills of oil, gas, salt water, or other noxious fluids will be immediately cleaned up and removed to an approved disposal site.

A chemical porta-toilet will be furnished with the drilling rig.

Garbage, trash, and other waste materials will be collected in a portable, self-contained, fully enclosed trash cage during operations. No trash will be burned on location.

All debris and other waste material not contained in the trash cage will be cleaned up and removed from the location immediately after removal of the drilling rig.

Any open pits will be fenced during the operations. The fencing will be maintained until such time as the pits are backfilled.

No chemicals subject to reporting under SARA Title III (hazardous materials) in an amount greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.

8. **Ancillary Facilities:**

None are anticipated.

9. **Well Site Layout:** (See Location Layout Diagram)

The attached Location Layout Diagram describes drill pad cross-sections, cuts and fills, and locations of the mud tanks, reserve pit, flare pit, pipe racks, trailer parking, spoil dirt stockpile(s), and surface material stockpile(s). *This section is subject to modification as a result of the on-site inspection.*

Please see the attached diagram to describe rig orientation, parking areas, and access roads.

If it is determined that a pit liner will be used at the on-site inspection, the reserve pit will be lined, and when the reserve pit is closed, the pit liner will be buried below plow depth.

RECEIVED

SEP 25 2000

DIVISION OF
OIL, GAS AND MINING

All pits will be fenced according to the following minimum standards:

39 inch net wire will be used with at least one strand of barbed wire on top of the net wire. Barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence.

The net wire shall be no more than two inches above the ground. The barbed wire shall be three inches over the net wire. Total height of the fence shall be at least 42 inches.

Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times.

Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any 2 fence posts shall be no greater than 16 feet.

All wire shall be stretched, by using a stretching device, before it is attached to corner posts.

The reserve pit fencing will be on three sides during drilling operations, and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.

10. Plans for Reclamation of the Surface:

Producing Location:

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, materials, trash, and debris not required for production.

Immediately upon well completion, any hydrocarbons in the pit shall be removed in accordance with 43 CFR 3162.7-1.

If a plastic, nylon reinforced liner is used, it shall be torn and perforated before backfilling of the reserve pit.

Before any dirt work associated with location restoration takes place, the reserve pit shall be as dry as possible. All debris in it will be removed. Other waste and spoil materials will be disposed of immediately upon completion of operations.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximate natural contours. The reserve pit will be reclaimed within 90 days from the date of well completion, weather permitting.

To prevent surface water (s) from standing (ponding) on the reclaimed reserve pit area, final reclamation of the reserve pit will consist of "mounding" the surface three feet above surrounding ground surface to allow the reclaimed pit area to drain effectively.

Upon completion of backfilling, leveling, and recontouring, the stockpiled topsoil will be spread evenly over the reclaimed area(s).

RECEIVED

SEP 25 2000

DIVISION OF
OIL, GAS AND MINING

Dry Hole/Abandoned Location:

Abandoned well sites, roads, and other disturbed areas will be restored as near as practical to their original condition. Where applicable, these conditions include the re-establishment of irrigation systems, the re-establishment of appropriate soil conditions, and re-establishment of vegetation as specified.

All disturbed surfaces will be recontoured to the approximate natural contours, with reclamation of the well pad and access road to be performed as soon as practical after final abandonment. Reseeding operations will be performed after completion of other reclamation operations.

11. Surface Ownership:

State of Utah
SITLA
675 East 500 South
Salt Lake City, UT 84102-2818

12. Other Information:

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, the approved Plan of Operations, and any applicable Notice of Lessees. The Operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished to the field representative to ensure compliance.

The Operator will control noxious weeds along Rights-Of-Way for roads, pipelines, well sites, or other applicable facilities.

A Class III archaeological survey was conducted by AERC , this report will be submitted when the report becomes available.

RECEIVED**SEP 25 2009****DIVISION OF
OIL, GAS AND MINING**

13. Lessee's or Operators's Representative & Certification:

Cheryl Cameron
Sr. Regulatory Analyst
Coastal Oil & Gas Corporation
P.O. Box 1148
Vernal, UT 84078
(435) 781-7023

Tom Young
Drilling Manager
Coastal Oil & Gas Corporation
9 Greenway Plaza, Suite 2770
Houston, TX 77046
(713) 418-4156


Certification: All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice to Lessees.

The Operator will be fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

Coastal Oil & Gas Corporation is considered to be the operator of the subject well. Coastal Oil & Gas Corporation agrees to be responsible under terms and conditions of the lease for the operations conducted upon leased lands.

Bond coverage pursuant to 43 CFR 3104 for lease activities is being provided by Coastal Oil & Gas Corporation Bond #102103.

I hereby certify that I, or persons under my supervision, have inspected the proposed drill site and access route, that I am familiar with the conditions that currently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed by the Operator, its contractors, and subcontractors in conformity with this plan and the terms and conditions under which it is approved.


Cheryl Cameron


9/14/00

Date

RECEIVED

SEP 25 2000

DIVISION OF
OIL, GAS AND MINING



LEGEND:

○ PROPOSED LOCATION

COASTAL OIL & GAS CORP.

NBU #359

SECTION 29, T10S, R21E, S.L.B.&M.

1220' FNL 2035' FEL



Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813




TOPOGRAPHIC
 MAP

8 1700
 MONTH DAY YEAR

SCALE: 1:100,000 | DRAWN BY: C.G. | REVISED: 00-00-00

A
 TOPO



LEGEND:

----- PROPOSED ACCESS ROAD
 _____ EXISTING ROAD

COASTAL OIL & GAS CORP.

NBU #359
SECTION 29, T10S, R21E, S.L.B.&M.
1220' FNL 2035' FEL



Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813




**TOPOGRAPHIC
MAP**

8 17 00
 MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: C.G. REVISED: 00-00-00

B
 TOPO

R
21
E



T10S

LEGEND:

- | | |
|-------------------|-------------------------|
| ⊗ DISPOSAL WELLS | ⊗ WATER WELLS |
| ● PRODUCING WELLS | ⊗ ABANDONED WELLS |
| ⊗ SHUT IN WELLS | ⊗ TEMPORARILY ABANDONED |



COASTAL OIL & GAS CORP.

NBU #359
SECTION 29, T10S, R21E, S.L.B.&M.
1220' FNL 2035' FEL




Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC
MAP

8 **17** **00**
MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: C.G. REVISED: 00-00-00





APPROXIMATE TOTAL PIPELINE DISTANCE = 3,800' +/-

LEGEND:

- EXISTING PIPELINE
- - - PROPOSED PIPELINE
- PROPOSED ACCESS

COASTAL OIL & GAS CORP.

NBU #359
SECTION 29, T10S, R21E, S.L.B.&M.
1220' FNL 2035' FEL

U E I S
Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813



TOPOGRAPHIC			8	21	00	D TOPO
MAP			MONTH	DAY	YEAR	
SCALE: 1" = 1000'		DRAWN BY: C.G.		REVISED: 00-00-00		

COASTAL OIL & GAS CORP.

LOCATION LAYOUT FOR

NBU #359

SECTION 29, T10S, R21E, S.L.B.&M.

1220' FNL 2035' FEL

FIGURE #1

Prevailing

Winds

SCALE: 1" = 50'
DATE: 08-03-00
Drawn By: D.R.B.

CONSTRUCT
DIVERSION
DITCH

NOTE:

Flare Pit is to be located
a min. of 100' from the
Well Head.

Approx.
Top of
Cut Slope

El. 199.2'
C-14.4'
(btm. pit)

FLARE PIT

C-2.8'
El. 197.6'

C-1.7'
El. 196.5'

C-1.4'
El. 196.2'

100'

100'

100'

100'

100'

100'

100'

100'

100'

100'

100'

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH

10' WIDE BENCH


COASTAL OIL & GAS CORP.

TYPICAL CROSS SECTIONS FOR

NBU #359



SECTION 29, T10S, R21E, S.L.B.&M.

1220' FNL 2035' FEL



DATE: 08-03-00

Drawn By: D.R.B.



RECEIVED

SEP 25 2000

DIVISION OF
OIL, GAS AND MINING

FIGURE #2

APPROXIMATE YARDAGES



CUT	
(6") Topsoil Stripping	= 1,200 Cu. Yds.
Remaining Location	= 5,330 Cu. Yds.
TOTAL CUT	= 6,530 CU.YDS.
FILL	= 3,790 CU.YDS.

EXCESS MATERIAL AFTER 5% COMPACTION	= 2,540 Cu. Yds.
Topsoil & Pit Backfill (1/2 Pit Vol.)	= 2,540 Cu. Yds.
EXCESS UNBALANCE (After Rehabilitation)	= 0 Cu. Yds.

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East • Vernal, Utah 84078 • (435) 789-1017

3,000 PSI

BOP STACK



RECEIVED.


SEP 25 2000

DIVISION OF
OIL, GAS AND MINING

COASTAL OIL & GAS CORPORATION

DRILLING PROGRAM

COMPANY NAME Coastal Oil & Gas Corporation DATE 9/13/00
WELL NAME NBU #359 TD 10,100' MD/TVD
FIELD NBU COUNTY Uintah STATE Utah ELEVATION 5,275' KB
SURFACE LOCATION 1,382' FNL & 2,150' FWL Sec 29 T10S-R21E BHL Straight Hole
OBJECTIVE ZONE(S) Wasatch, Mesaverde
ADDITIONAL INFO



COASTAL OIL & GAS CORPORATION
DRILLING PROGRAM

CASING PROGRAM

	SIZE	INTERVAL	WT.	GR.	CPLG.	DESIGN FACTORS		
						BURST	COLLAPSE	TENSION
SURFACE	8-5/8"	0-2,500'	32#	J-55	LTC	3,930	2,530	417,000
						2.80	2.16	2.32
PRODUCTION	4-1/2"	0-TD	11.6#	P-110	LTC	10,690	7,560	279,000
						2.32	1.31	1.28

- 1) Maximum Anticipated Surface Pressure (MASP) (Conductor and Surface Casings) = (Frac Gradient at Shoe - Gas Gradient (0.115 psi/ft))(TVD)
- 2) MASP (Int Casing) = Pore Pressure at Next Casing Point - (Gas Gradient x TVD of Next Casing Point x 0.67) - (Mud Weight x TVD x 0.052 x 0.33)
- 3) MASP (Prod Casing) = Pore Pressure - (Gas Gradient x TVD of Production Interval)
- (Burst Assumptions: FG @ 8-5/8" shoe = 13.0 ppg, Max Pore Pressure = 11 ppg Max MW)
- (Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing, 100,000 lbs overpull)

CEMENT PROGRAM


		FT. OF FILL	DESCRIPTION	SACKS	EXCESS*	WEIGHT	YIELD
SURFACE	LEAD	2,000'	Lite Class G + 2% CaCl2 + 0.25 lb/sk Flocele	420	50%	12.70	1.82
	TAIL	500'	Lite Class G + 2% CaCl2 + 0.25 lb/sk Flocele	200	75%	15.60	1.19
PRODUCTION	LEAD	3,970'	HiFill-Mod + 0.6% EX-1	480	100%	11.60	3.81
			+ 0.25 lb/sk Flocele + 0.2% FWCA				
			+ 10 lb/sk Gilsonite + 16% Gel				
			+ 1% HR-7 + 3% Salt				
	TAIL	6,130'	50/50 Poz +0.25 lb/sk Flocele	1920	75%	14.40	1.28
			+ 0.4% HALAD-322 + 2% Gel				
			+ 2% Microbond HT + 0.1% HR-5 + 5% Salt				

* or 15% over caliper

FLOAT EQUIPMENT & CENTRALIZERS

SURFACE	Guide shoe, 1 joint, float collar. Centralize first 3 joints & every other collar to surface. Thread lock FE up to and including pin end of float collar.
PRODUCTION	Guide shoe, 1 joint, float collar. Install 2 bow spring centralizers on the shoe joint and 1 on the next two joints. Then 1 centralizer every third joint to top of tail cement. Thread lock FE up to and including pin end of FC.

WELLHEAD EQUIPMENT



TREE	2-1/16" 5M
TUBING HEAD	11" 5M X 7-1/16" 10M
CASING SPOOL	
CASING SPOOL	13-5/8" 3M X 11" 5M
CASING HEAD	8-5/8" SOW X 11" 5M

SEP 25 2000

COASTAL OIL & GAS CORPORATION
DRILLING PROGRAM

BIT PROGRAM

ROCK BIT & PDC BIT PROGRAM						
INTERVAL	HOLE	BIT MFG & MODEL	GPM	SERIAL	NZLS	COMMENTS
Surface Hole	11"	STC F27 or Equiv.	Air	NEW	3 - 18's	Air / Air Mist
Production Hole	7-7/8"	Various Inserts / PDC's	350-400	NEW	3 - 18's	Air / Air Mist / Water

GEOLOGICAL DATA

LOGGING:

Depth	Log Type
SC - TD	Platform Express with Sonic

MUD LOGGER:
SAMPLES:
CORING:
DST:

SC - TD
As per Geology

RECEIVED

SEP 25 2000

DIVISION OF
OIL, GAS AND MINING

MUD PROGRAM

DEPTH	TYPE	MUD WT	WATER		TREATMENT
			LOSS	VISCOSITY	
0'-2,500'	Air Mist	NA	NA		
SC-TD	Mist/Water/Mud	8.5-11.0	NC - <10 cc's	30-45	Champion Corrosion Chemicals Polymer, Lime, Brine, Barite

ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,000 psi prior to drilling out. Test int. csg. to 1,500 psi prior to drilling out. 11" 5M with one 5M annular and 2 rams. Test to 5,000 psi (annular to 3,000 psi) prior to drilling out. Record on chart recorder & tour sheet. Function test rams on each trip. Maintain safety valve & inside BOP on rig floor at all times. Kelly to be equipped with upper & lower kelly valves. Corrosion treatment while drilling with air - RU160 then pump O₂ scavanger and proceed with scale inhibitor only. Run Totco survey every 1500' from surface casing shoe to TD. Maximum allowable hole angle is 5 degrees.

PROJECT ENGINEER: _____
Christa Yin

PROJECT MANAGER: _____
Darrell Molnar

DATE: _____

DATE: _____

CULTURAL RESOURCE EVALUATIONS OF SIX PROPOSED COASTAL WELL LOCATIONS (NB Units 357, 358, 359, 361, 366, & 367) IN THE EAST BENCH LOCALITY OF UINTAH COUNTY, UTAH

Report Prepared for Coastal Oil & Gas Corporation

Department of Interior Permit No.: Ut-54937

Utah State Permit No.: Ut00AF0504b

AERC Project 1656 (COG00-21)

Author of Report:

F. Richard Hauck, Ph.D



ARCHEOLOGICAL-ENVIRONMENTAL RESEARCH CORPORATION

181 North 200 West, Suite 5 -- Bountiful, Utah 84010

P.O. Box 853, Bountiful, Utah 84011

Phone: (801) 292-7061, 292-9668

FAX: (801) 292-9668

E-mail: ari@xmission.com Web page: www.ari-aerc.org

RECEIVED

SEP 25 2000

September 12, 2000

DIVISION OF
OIL, GAS AND MINING

ABSTRACT

An intensive cultural resource evaluation has been conducted for Coastal Oil & Gas Corporation of seven well locations (NB Units Nos. 351, 357, 358, 359, 361, 366, and 367) and the related pipeline and access corridors in the East Bench locality (see Maps 1 through 5) of Uintah County, Utah. About 84 acres of public lands in the locality were examined by AERC archaeologists during evaluations conducted on September 7, 2000.

No previously recorded cultural resources will be adversely affected by the proposed developments. Known cultural sites situated in the general region are not endangered by direct adverse effect relative to these developments because of their distance from the present project areas.

One isolated find was observed during evaluations in the vicinity of well pad NB Unit No. 357. This artifact consisted of a chalcedony biface tip; it was not collected.

AERC recommends project clearance based upon adherence to the stipulations noted in the final section of this report.

RECEIVED

SEP 25 2000

DIVISION OF
OIL, GAS AND MINING

TABLE OF CONTENTS

	page
Abstract	ii
Table of Contents	iii
List of Maps of the Project Area	iv
Colorado Resource Survey Management Information Form	v
General Information	1
Project Location	1
Environment	7
File Search	7
Study Objectives and Expected Results	8
Site Potential in the Development Zone	8
Field Evaluations	9
Methodology	9
Site Significance Criteria	9
Results of the Inventory	10
Conclusion and Recommendations	10
Bibliography	11

RECEIVED

SEP 25 2000

DIVISION OF
OIL, GAS AND MINING

LIST OF MAPS OF THE PROJECT AREA

	page
Map 1: General Project Area in Uintah County, Utah	2
Map 2: Cultural Resource Survey of Proposed Well Locations in Uintah County, Utah	3
Map 3: Cultural Resource Survey of Proposed Well Locations in Uintah County, Utah	4
Map 4: Cultural Resource Survey of Proposed Well Locations in Uintah County, Utah	5
Map 5: Cultural Resource Survey of Proposed Well Locations in Uintah County, Utah	6

RECEIVED

SEP 25 2000

DIVISION OF
OIL, GAS AND MINING

GENERAL INFORMATION

The Coastal Oil & Gas 2000 development program involves the construction of six well locations (NBU Unit Nos. 351, 357, 358, 359, 361, 366, and 367) and their related pipeline and access corridors in the East Bench locality (see Maps 1 through 5) of Uintah County, Utah. About 84 acres of public lands in the locality were examined by AERC archaeologists during evaluations conducted on September 7, 2000. The project area is on federal land administered by the Bureau of Land Management office in Vernal, Utah. The project was conducted under Department of the Interior Permit No. UT-54937, which expires on January 31, 2001. The Utah State permit for this project is UT-00-AF-0504b.

The purpose of the field study and this report is to identify and document cultural site presence and determine cultural resource National Register eligibility relative to established criteria (cf., 36 CFR 60.6). Federal regulations require an environmental assessment of the potential development area. One aspect of such an assessment involves a Class I (records search) and Class III (intensive survey) archaeological evaluation of the development area. Such investigations are accomplished in compliance with the Antiquities Act of 1906, the Historic Sites Act of 1935, Section 106 of the National Historic Preservation Act of 1966, as amended, the National Environmental Policy Act of 1969, the Federal Land Policy and Management Act of 1976, the Archaeological Resources Protection Act of 1979, the Native American Religious Freedom Act of 1978, the Historic Preservation Act of 1980, and Executive Order 11593.

To accomplish this investigation, a total of 84 acres was examined by the archaeologists, who walked a series of 10 to 15 meter-wide transects within the six staked ten acre well pad zones and along the 100 foot-wide access/pipeline corridors.

All field notes and report information concerning this project are filed at the AERC office in Bountiful, Utah.

Project Location

The project area is to the south of Vernal, Utah. The developments are located on East Bench on the Archy Bench and Big Pack Mtn NE USGS quads. The proposed development locations are situated as follows:

NBU No. 357 (see Map 2) is located in the SW of the SW quarter of Section 15, Township 10 South, Range 21 East, Salt Lake Base & Meridian. The combined access/pipeline corridor links into the existing system within the ten acre survey area.

NBU No. 358 (see Map 2) is located in the SE of the SW quarter of Section 16, Township 10 South, Range 21 East, Salt Lake Base & Meridian. This well pad is located along an existing road. The pipeline corridor exits from the east side of the pad and extends north for ca. .4 mile where it enters into the existing system.

RECEIVED

SEP 25 2000

**DIVISION OF
OIL, GAS AND MINING**

MAP 1
GENERAL PROJECT AREA IN
UINTAH COUNTY, UTAH



PROJECT: COG00-21
SCALE: 1: 200,650
DATE: 9/12/00



PROJECT AREA

TOWNSHIP: multiple
RANGE: multiple
MERIDIAN: multiple


Utah Geological and Mineral Survey
 Map 43 1977

Physiographic Subdivisions of Utah
 by W.L. Stokes

SEP 25 2000

DIVISION OF
 OIL, GAS AND MINING

PROJECT: COG00-21
 SCALE: 1:24,000
 QUAD: Big Pack Mtn. NE
 DATE: September 12, 2000



TOWNSHIP: 10 South
 RANGE: 21 East
 MERIDIAN: Salt Lake
 B. & M.

LEGEND



Well
 Location
 Survey
 Area




Combined
 Access
 Route &
 Pipeline
 Corridor



Pipeline
 Corridor

PROJECT: COG00-21
SCALE: 1:24,000
QUAD: Big Pack Mtn. NE
DATE: September 12, 2000



TOWNSHIP: 10 South
RANGE: 21 East
MERIDIAN: Salt Lake
B. & M.

LEGEND



Well
Location




Access
Route




Access
Route

PROJECT: COG00-21
SCALE: 1:24,000
QUAD: Archy Bench
DATE: September 12, 2000




TOWNSHIP: 10 South
RANGE: 22 East
MERIDIAN: Salt Lake
B. & M.

LEGEND




PROJECT: COG00-21
SCALE: 1:24,000
QUAD: Archy Bench
DATE: September 12, 2000



TOWNSHIP: 10 South
RANGE: 22 East
MERIDIAN: Salt Lake
B. & M.

LEGEND



Well
Location
Survey
Area



Pipeline
Corridor

NBU No. 359 (see Map 3) is located in the NW of the NE quarter of Section 29, Township 10 South, Range 21 East, Salt Lake Base & Meridian. Both the pipeline and the access road exit the well pad to the south. The road continues south for ca. .3 mile to link with the existing roadway. The .7 mile-long pipeline curves to the northwest to eventually link with an existing pipeline in the NW of the SW quarter of adjacent Section 20.

NBU No. 361 (see Map 5) is located in the NW of the NW quarter of Section 32, Township 10 South, Range 22 East, Salt Lake Base & Meridian. This well pad is located along an existing road. The pipeline corridor exits from the well pad and extends in a northerly course for ca. .4 mile to link into the existing pipeline system.

NBU No. 366 (see Map 2) is located in the NW of the NW quarter of Section 10, Township 10 South, Range 21 East, Salt Lake Base & Meridian. A .1 mile-long combined access/pipeline corridor extends northeast from the proposed well location the existing road. The pipeline continues to the northeast for ca. .2 mile to enter the main network.

NBU No. 367 (see Map 4) is located in the NE of the SW quarter of Section 11, Township 10 South, Range 22 East, Salt Lake Base & Meridian. This location immediately adjacent to an existing access road and pipeline.

Environment

The elevations for the proposed well locations range from 5060 to 5480 feet above sea level. Ephemeral drainages in the project area are associated with tributaries that drain southward into the Green River or the White River.

The vegetation of the project locality is primarily associated with the sage rangeland environment. Vegetation species commonly found in this general area include *Artemisia tridentata*, *Chrysothamnus nauseosus*, *Atriplex spp.*, *Sarcobatus vermiculatus*, *Opuntia polyacantha*, *Ephedra spp.* and various grasses including *Hordeum jubatum* and *Bromus tectorum*. Surrounding vegetation consists of *Artemisia tridentata* and *Ephedra spp.*

The project area is situated in the Uinta Formation and within the Colorado Plateau physiographic province.

File Search

Records searches were conducted in the Vernal BLM office on August 30, 2000 and at the SHPO in Salt Lake City on August 29, 2000. Earlier projects conducted in this general area include the following: 78-AF-0345, 81-BC-0721, 86-MM-0704, 91-GB-0796b, 97-MM-0157.

Two sites located by the searches, 42UT1792 and 42UT1953, are outside the current project area, and will not be affected by the proposed developments.

Other archaeological consultants in addition to AERC and the local BLM archaeologists that have worked in the project area include personnel from Montgomery Archaeological Consultants, Alpine Archaeological Consultants, Nickens and Associates, Brigham Young University, and Grand River Institute.

Previous evaluations and area inventories indicate the occupation of the general project area has included prehistoric occupations (cultural affiliation unknown). For a comprehensive treatment of the prehistory and history of this general cultural area see Archaeological Evaluations in the Northern Colorado Plateau Cultural Area (Hauck 1991)

The National Register of Historic Places has been consulted and no registered historic or prehistoric properties will be affected by the proposed development.

STUDY OBJECTIVES AND EXPECTED RESULTS

The purpose of this evaluation was to identify, evaluate, and record any cultural resources encountered within the proposed Coastal Oil & Gas development area; to determine the significance of identified resources; and to recommend appropriate mitigation measures relative to the preservation of resources found to be endangered by the project.

These objectives were accomplished by seeking surface indications of cultural resource presence. Cultural resource sites would be identified by the presence of three or more associated artifacts and/or features that demonstrate the presence of patterned human activity and then recorded on the appropriate IMACS forms.

The previous identification of prehistoric and historic cultural resources in the general area indicated a possibility that additional resources could be discovered during these evaluations.

No constraints, e.g., snow cover, dense vegetation, difficult weather, were imposed on the evaluation of this well location. The project was completed on September 6, 2000.

Site Potential in the Project Development Zone

Previous archaeological evaluations in this general region have resulted in the identification and recording of limited archaeological resources in these four localities. Such prehistoric sites as have been recorded demonstrate a definitive selection of environmental community and water resource.

FIELD EVALUATIONS

Methodology

To accomplish an intensive evaluation of the project areas shown on the maps, the archaeologists walked a series of 10 to 15 meter-wide transects within each ten acre staked location and along the various 30 meter-wide access/pipeline corridors. All together, a 100% pedestrian survey was conducted of about 84 acres.

When cultural materials are discovered, the archaeologist conducts a careful search of the vicinity to locate and evaluate features, artifact types and concentrations, site spatial associations, and temporal identifications. Sites and isolates are then recorded on the appropriate forms, locations sketched, perimeters marked on a topographic map, and photographs taken. Copies of these reports are provided to the appropriate State and Federal offices as attachments to the final report.

In certain instances, the cultural sites are then evaluated for depth potential utilizing AERC's portable Ground Penetrating Radar (GPR) computerized system (SIR-2 manufactured by Geophysical Survey Systems, Inc. [GSSI] of North Salem, New Hampshire). GPR was not used during this project.

Cultural sites are then evaluated for significance utilizing the standards described below and mitigation recommendations are considered as a means of preserving significant resources which may be situated within the development zone.

Site Significance Criteria

The various criteria relative to establishing the eligibility of prehistoric and historic cultural sites preparatory to their potential nomination to the National Register of Historic Places have been outlined as follows in the National Register's Criteria for Evaluation as established in Title 36 CFR 60.6:

The quality of significance in American ... archaeology ... and culture is present in ... sites ... that possess integrity of location, design, setting, materials, workmanship, feeling, and association and:

- a. That are associated with events that have made a significant contribution to the broad patterns of our history; or*
- b. that are associated with the lives of persons significant in our past; or*
- c. that embody the distinctive characteristics of a type, period, or method of construction ... ; or*
- d. that have yielded, or may be likely to yield, information important in prehistory or history.*

In addition to satisfying one or more of these general conditions, a significant cultural resource site in Utah will generally be considered as being eligible for inclusion in the National

Register if it still retains its integrity and can contribute to our current state of knowledge concerning chronology, cultural relationships, origins, and cultural life ways of prehistoric or historic groups in the area.

In a final review of any site's cultural significance, the site must possess integrity and at least one of the above criteria to be considered eligible for nomination to the National Record of Historic Places.

Results of the Inventory

During the survey of the various corridors and well locations referenced in this report, no cultural resources were encountered.


One isolated find was observed in the vicinity of well pad NBU No. 357. This artifact consisted of a chalcedony biface tip which was not collected.

No previously recorded cultural resources will be adversely affected by the proposed developments. Known cultural sites situated in the general region are not endangered by direct adverse effect relative to these developments because of their distance from the present project areas.

CONCLUSION AND RECOMMENDATIONS

AERC recommends that a cultural resource clearance be granted to Coastal Oil & Gas Corporation relative to the development of NB Units Nos. 357, 358, 359, 361, 366, and 367 based upon adherence to the following stipulations:

1. All vehicle traffic, personnel movement, and construction should be confined to the flagged location, pipeline corridor or access route examined as referenced in this report, or to existing routes;
2. All personnel should refrain from collecting artifacts or from disturbing any cultural resources in the area; and
3. The principal authority should be consulted should cultural remains from subsurface deposits be exposed during exploratory and developmental work or if the need arises to relocate or otherwise alter the development area.


F. Richard Hauck, Ph.D.
President and Principal
Investigator

BIBLIOGRAPHY

Hauck, F. Richard

- 1991 Archaeological Evaluations on the Northern Colorado Plateau Cultural Area, AERC Paper No. 45, Archeological-Environmental Research Corporation, Bountiful.
- 2000 Cultural Resource Evaluations of Four Proposed Coastal Well Locations (CIGE Units Nos. 251, 252, 253, & 254) in the Cottonwood Wash Locality of Uintah County, Utah. Report prepared for Coastal Oil & Gas Corporation (COG00-22), Archeological-Environmental Research Corporation, Bountiful.

Hauck, F.R. and Garth Norman

- 1980 Final Report on the Mapco River Bend Cultural Mitigation Study. AERC Paper No. 18, of the Archeological-Environmental Research Corporation, Bountiful.

Stokes, W.L.

- 1977 Physiographic Subdivisions of Utah. Map 43, Utah Geological and Mineral Survey, Salt Lake City.

U.S.
Department of the Interior
Bureau of Land Management
Utah State Office
(AERC FORMAT)
Summary Report of
Inspection for Cultural Resources

Project
Authorization No UT-00-AF-0504b

Report Acceptable Yes ___ No ___
Mitigation Acceptable Yes ___ No ___
Comments: _____

Cultural Resource Evaluation of Six Proposed Well Locations (NB Unit Nos. 357, 358, 359, 361, 366, 367) in Uintah County, Utah

1. Report Title
2. Development Company Coastal Oil & Gas Corporation
3. Report Date 9/12/00 4. Antiquities Permit No. UT-00-54937
5. Responsible Institution AERC COG00-21 County Uintah
6. Fieldwork Location: TWN ..10 S . RNG .. 21 E . Section 10, 15, 16, 29, , & TWN ..10 S . RNG .. 22 E . Sections 11, 29, 32,
7. Resource Area BC.

8. Description of Examination Procedures: *The archeologists, F.R. Hauck Alan Hutchinson and Greg Stoehr, intensively examined the six 10 acre parcels and associated access/pipeline routes (100 feet-wide) by walking a series of 15 to 20 meter-wide transects.*

9. Linear Miles Surveyed

10. Inventory Type .I.

and/or

Definable Acres Surveyed

R = Reconnaissance

and/or

I = Intensive

Legally Undefinable

S = Statistical Sample

Acres Surveyed 84

11. Description of Findings:

12. Number Sites Found .0. (No sites = 0)

13. Collection: .N. (Y = Yes, N = No)

14. Actual/Potential National Register Properties Affected:

The National Register of Historic Places (NRHP) has been consulted and no registered properties will be affected by the proposed development.

15. Literature Search, Location/ Date: Utah SHPO 08-29-00 Vernal BLM 08-30-00

16. Conclusion/ Recommendations:

AERC recommends that a cultural resource clearance be granted to Coastal Oil & Gas Corporation for these proposed developments based on the following stipulations:

- 1. All vehicular traffic, personnel movement, construction and restoration operations should be confined to the existing roadways and/or evaluated corridors.*
- 2. All personnel should refrain from collecting artifacts and from disturbing any significant cultural resources in the area.*
- 3. The authorized official should be consulted should cultural remains from subsurface deposits be exposed during construction work or if the need arises to relocate or otherwise alter the location of the development.*

17. Signature of Administrator & Field Supervisor:

Administrator:

Field

Supervisor:

WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 09/25/2000

API NO. ASSIGNED: 43-047-33706

WELL NAME: NBU 359

OPERATOR: COASTAL OIL & GAS CORP (N0230)

CONTACT: CHERYL CAMERON

PHONE NUMBER: 435-781-7023

PROPOSED LOCATION:

NWNE 29 100S 210E

SURFACE: 1220 FNL 2035 FEL

BOTTOM: 1220 FNL 2035 FEL

UINTAH

NATURAL BUTTES (630)

LEASE TYPE: 3-State

LEASE NUMBER: ML-21330

SURFACE OWNER: 3-State

PROPOSED FORMATION: MVRD

INSPECT LOCATN BY: / /

Tech Review	Initials	Date
Engineering	<i>RJK</i>	10-31-00
Geology	<i>Patm</i> Revision	1/2/01
Surface		

RECEIVED AND/OR REVIEWED:

☒ Plat
☒ Bond: Fed[] Ind[] Sta[3] Fee[]
(No. 10 21 03)
N Potash (Y/N)
Y Oil Shale (Y/N) *190 - 5 (B)
☒ Water Permit
(No. 43-8496)
N RDCC Review (Y/N)
(Date:)
N/A Fee Surf Agreement (Y/N)

LOCATION AND SITING:

 R649-2-3. Unit Natural Buttes
 R649-3-2. General
Siting: _____
 R649-3-3. Exception
☒ Drilling Unit
Board Cause No: 173-14
Eff Date: 12-2-99
Siting: 460' fr Unit Boundary & Uncomm. Tract
 R649-3-11. Directional Drill

COMMENTS: Need Presite. (10-12-2000)

STIPULATIONS: ① STATEMENT OF BASIS
② OIL SHALE




Utah Oil Gas and Mining

OPERATOR: COASTAL O&G CORP (N0230)

FIELD: NATURAL BUTTES (630)

SEC. 29, T10S, R21E,

COUNTY: UINTAH UNIT: NATURAL BUTTES
CAUSE: 173-14



PREPARED BY: LCORDOVA
DATE: 25-SEPTEMBER-2000

United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, Utah 84145-0155

IN REPLY REFER TO:
3160
(UT-922)

September 27, 2000

Memorandum

To: Assistant District Manager Minerals, Vernal District
From: Michael Coulthard, Petroleum Engineer
Subject: 2000 Plan of Development Natural Buttes Unit,
Uintah County, Utah.

Pursuant to email between Lisha Cordova, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management. The following wells are planned for calendar year 2000 within the Natural Buttes Unit, Uintah County, Utah.

Api Number	Well	Location
43-047-33708	NBU 358	Sec. 16, T10S, R21E 0872 FSL 1950 FWL
43-047-33706	NBU 359	Sec. 29, T10S, R21E 1220 FNL 2035 FEL
43-047-33705	NBU 361	Sec. 32, T10S, R22E 0491 FNL 0917 FWL
43-047-33707	NBU 367	Sec. 11, T10S, R22E 2500 FSL 2220 FWL

This office has no objection to permitting the wells at this time.

/s/ Michael L. Coulthard

bcc: File - Natural Buttes Unit
Division of Oil Gas and Mining
Agr. Sec. Chron
Fluid Chron

MCoulthard:mc:9-27-0

ON-SITE PREDRILL EVALUATION

Division of Oil, Gas and Mining

OPERATOR: Coastal Oil & Gas Corporation
WELL NAME & NUMBER: NBU #359
API NUMBER: 43-047-33706
LEASE: ML-21330 FIELD/UNIT: Natural Buttes
LOCATION: 1/4, 1/4 NW/NE Sec: 29 TWP: 10S RNG: 21E 1220' FNL 2035' FEL
LEGAL WELL SITING: 460 feet from a unit boundary.
GPS COORD (UTM): 12 621915E; 4420131N
SURFACE OWNER: SITLA

PARTICIPANTS

Dennis L. Ingram (DOGM); Carroll Estes, Carroll Williams, Debbie Harris, Don Detterera, and Clay Enerson (Coastal Oil & Gas Corporation); Gary Scott (Jackson Construction); Robert Kay (Uintah Engineering); John Fausett (Fausett Inc.); Tim Justic (L&L Oilwell Service).

REGIONAL/LOCAL SETTING & TOPOGRAPHY

Proposed site is set in Natural Buttes Field approximately 4.5 miles east of Willow Creek on western bench along side of Cottonwood Creek.

SURFACE USE PLAN

CURRENT SURFACE USE: Domestic grazing and wildlife use.

PROPOSED SURFACE DISTURBANCE: Approximately 0.3 miles of new access Road and location measuring 170'x 325' plus reserve pit.

LOCATION OF EXISTING WELLS WITHIN A 1 MILE RADIUS: NBU 85D; CIGE 20; CIGE 59

LOCATION OF PRODUCTION FACILITIES AND PIPELINES: All production Facilities such as tanks, separator and dehys shall remain on location. Pipeline shall run northwest along western side of wash for approximately 1.0 miles and tie into existing line north of CIGE 20.

SOURCE OF CONSTRUCTION MATERIAL: Native cut and fill using borrowed material.

ANCILLARY FACILITIES: None requested.

WASTE MANAGEMENT PLAN:

Submitted to DOGM with Application to drill

ENVIRONMENTAL PARAMETERS

AFFECTED FLOODPLAINS AND/OR WETLANDS: Location is on bench out of Potential flood plain.

FLORA/FAUNA: Shadscale, prickly-pear cactus, wild grass typical of region (good ground cover). Antelope, deer, cougar, coyote, rabbit, and other small birds and mammals.

SOIL TYPE AND CHARACTERISTICS: Tan, light brown sandy loam with some Clay present.

SURFACE FORMATION & CHARACTERISTICS: Uinta Formation

EROSION/SEDIMENTATION/STABILITY: Active erosion present, sedimentation shows gilsonite from up wash, no stability problems anticipated.

PALEONTOLOGICAL POTENTIAL: None observed during onsite investigation

RESERVE PIT

CHARACTERISTICS: In cut on southwest corner and upwind of prevailing wind, measuring 100'x 100'x 10' deep with 9650 bbl capacity.

LINER REQUIREMENTS (Site Ranking Form attached): _____

SURFACE RESTORATION/RECLAMATION PLAN

According to SITLA at time of reclamation.

SURFACE AGREEMENT: Yes

CULTURAL RESOURCES/ARCHAEOLOGY: A.E.R.C.

OTHER OBSERVATIONS/COMMENTS

Small chunks of gilsonite along wash, or proposed access, into location which has washed down dry streambed during past storms. Sandstone outcroppings along wash bed east of proposed location; also noted sandstone outcropping on adjacent wash east of wash.

ATTACHMENTS:

Photos of staking and location surface.

Dennis L. Ingram
DOGM REPRESENTATIVE

10/12/00 11:00 am
DATE/TIME

**Evaluation Ranking Criteria and Ranking Score
For Reserve and Onsite Pit Liner Requirements**

<u>Site-Specific Factors</u>	<u>Ranking</u>	<u>Site Ranking</u>
Distance to Groundwater (feet)		
>200	0	
100 to 200	5	
75 to 100	10	
25 to 75	15	
<25 or recharge area	20	<u>5</u>
Distance to Surf. Water (feet)		
>1000	0	
300 to 1000	2	
200 to 300	10	
100 to 200	15	
< 100	20	<u>0</u>
Distance to Nearest Municipal Well (feet)		
>5280	0	
1320 to 5280	5	
500 to 1320	10	
<500	15	<u>0</u>
Distance to Other Wells (feet)		
>1320	0	
300 to 1320	10	
<300	20	<u>0</u>
Native Soil Type		
Low permeability	0	
Mod. permeability	10	
High permeability	20	<u>20</u>
Fluid Type		
Air/mist	0	
Fresh Water	5	
TDS >5000 and <10000	15	
TDS >10000 or Oil Base	20	
Mud Fluid containing high levels of hazardous constituents		<u>0</u>
Drill Cuttings		
Normal Rock	0	
Salt or detrimental	10	<u>0</u>
Annual Precipitation (inches)		
<10	0	
10 to 20	5	
>20	10	<u>0</u>
Affected Populations		
<10	0	
10 to 30	6	
30 to 50	8	
>50	10	<u>0</u>
Presence of Nearby Utility Conduits		
Not Present	0	
Unknown	10	
Present	15	<u>0</u>
Final Score (Level II Sensitivity)		<u>25 points</u>

UTAH DIVISION OF WATER RIGHTS
WATER RIGHT POINT OF DIVERSION PLOT CREATED TUE, OCT 31, 2000, 11:58 AM
PLOT SHOWS LOCATION OF 2 POINTS OF DIVERSION

PLOT OF AN AREA WITH A RADIUS OF 10000 FEET FROM A POINT
FEET, FEET OF THE CT CORNER,
SECTION 29 TOWNSHIP 10S RANGE 21E SL BASE AND MERIDIAN

PLOT SCALE IS APPROXIMATELY 1 INCH = 4000 FEET

N O R T H

**

**

**

**

*

*

*

*

*

*

*

*

1

0

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*


*


*


*


*


MAP CHAR	WATER RIGHT	CFS	QUANTITY AND/OR	AC-FT	SOURCE DESCRIPTION or WELL INFO DIAMETER	DEPTH	YEAR LOG	NORTH	EAST	POINT OF DIVERSION DESCRIPTION CNR SEC	TWN	RNG B&M	
0	49 392	.1700		.00	16	2200 - 3300		S	2900 W	1300	NE 19 10S	21E SL	
		WATER USE(S): DOMESTIC OTHER								PRIORITY DATE: 02/20/198			
		Magic Circle Energy Corp.(C/O Synfuels E 1667 Cole Blvd. Bldg. #19, Suite 400								Golden			
1	49 392	.1700		.00	16	2200 - 3300		N	1930 E	400	SW 19 10S	21E SL	
		WATER USE(S): DOMESTIC OTHER								PRIORITY DATE: 02/20/198			
		Magic Circle Energy Corp.(C/O Synfuels E 1667 Cole Blvd. Bldg. #19, Suite 400								Golden			














October 31, 2000

State of Utah
Division of Oil Gas & Mining
1594 West North Temple, Suite 1210
P.O. Box 145801
Salt Lake City, UT 84114


ATTENTION: Lisha Cordova

Dear Lisha,

The location for the NBU #359 proposed well to be drilled in the NW/NE Sec. 29, T10S, R21E, Uintah County, Utah is 1220' FNL & 2035' FEL of said Sec. 29. This location is not within 460 feet from the boundary of the Natural Buttes Unit, nor is it within 460 feet of any non-committed tract lying within the boundaries of the Unit.

If you have questions or need additional information, please do not hesitate to call me,
(435) 781-7023.

Sincerely,


Cheryl Cameron
Sr. Regulatory Analyst

Coastal Oil & Gas Corporation

A SUBSIDIARY OF THE COASTAL CORPORATION
1368 S 1200 E • P.O. BOX 1148 • VERNAL, UT 84078 • 435/789-4433 • FAX 435/789-4436

DIVISION OF OIL, GAS AND MINING
APPLICATION FOR PERMIT TO DRILL
STATEMENT OF BASIS

Operator Name: Coastal Oil & Gas Corporation
Name & Number: NBU #359
API Number: 43-047-33706
Location: 1/4, 1/4 NW/NE Sec. 29 T. 10S R. 21E

Geology/Ground Water:

Coastal proposes to set 25' of surface casing at this location. The depth to the base of the moderately saline water at this location is estimated to be at a depth of 4,100'. A search of Division of Water Rights records shows 2 water wells within a 10,000 foot radius of the center of section 29. These are listed as being used for domestic use. Both are approximately a mile or more in distance from the proposed well. Production depth of these wells is 2200 and 3300'. The surface formation at this site is the Uinta Formation. The Uinta Formation is made up of interbedded shales and sandstones. The sandstones are mostly lenticular and discontinuous and should not be a significant source of useable ground water. Production casing cement should be brought to above the base of the moderately saline groundwater in order to isolate it from fresher waters uphole.

Reviewer: Brad Hill
Date: 10/31/2000

Surface:

A presite investigation was done on 10/12/00 after being rained out the day before. The surface and minerals belong to Sitla. Ed Bonner with SITLA was notified by DOGM of the onsite schedule but was unable to attend. This well site is within the boundary of a federal drilling unit. Sandstone outcropping were observed on shelf just east of location dropping into wash at the same level of proposed reserve pit; sandstone ledges were also present on adjacent sides of wash indicated fractured rock is probable when constructing same. Old Gilsonite mines are also documented on topo map approximately 0.3 miles south/southwest of location. Low water crossings were acceptable for access into location along roadway with culverts optional for drainage. A shallow drainage was also noted running west to east across location and should be diverted north (as the location dips that direction) around location and tied back into wash.

Reviewer: Dennis L. Ingram
Date: October 12, 2000

Conditions of Approval/Application for Permit to Drill:

1. A 12 mil pit liner shall be required to line reserve pit because of probable fractured sandstone below surface of location and potential ground water along dry wash.

Well name:

10-00 Coastal NBU #359Operator: **Coastal**String type: **Surface**

Project ID:

43-047-33706

Location: **Uintah County****Design parameters:****Collapse**

Mud weight: 9.000 ppg

Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No

Surface temperature: 75 °F

Bottom hole temperature: 110 °F

Temperature gradient: 1.40 °F/100ft

Minimum section length: 250 ft

Cement top: Surface

Burst

Max anticipated surface

pressure: 0 psi

Internal gradient: 0.468 psi/ft

Calculated BHP 1,169 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)

8 Round LTC: 1.80 (J)

Buttress: 1.60 (J)

Premium: 1.50 (J)

Body yield: 1.50 (B)

Non-directional string.

Re subsequent strings:

Next setting depth: 7,500 ft

Next mud weight: 9.000 ppg

Next setting BHP: 3,506 psi

Fracture mud wt: 19.250 ppg

Fracture depth: 7,500 ft

Injection pressure 7,500 psi

Tension is based on buoyed weight.

Neutral point: 2,166 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost ()
1	2500	8.625	32.00	J-55	LT&C	2500	2500	7.875	25641
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	1169	2530	2.16	1169	3930	3.36	69	417	6.02 J

Prepared RJK
by: Utah Dept. of Natural ResourcesDate: October 31, 2000
Salt Lake City, Utah**ENGINEERING STIPULATIONS: NONE**

Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Collapse is based on a vertical depth of 2500 ft, a mud weight of 9 ppg. The casing is considered to be evacuated for collapse purposes.

In addition, burst strength is biaxially adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

Well name:

10-00 Coastal NBU #359Operator: **Coastal**String type: **Production**

Project ID:

43-047-33706Location: **Uintah County****Design parameters:****Collapse**

Mud weight: 11.000 ppg

Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No

Surface temperature: 75 °F

Bottom hole temperature: 216 °F

Temperature gradient: 1.40 °F/100ft

Minimum section length: 250 ft

Cement top: 3,100 ft

BurstMax anticipated surface
pressure: 0 psi

Internal gradient: 0.571 psi/ft

Calculated BHP 5,771 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)

8 Round LTC: 1.80 (J)

Buttress: 1.60 (J)

Premium: 1.50 (J)

Body yield: 1.50 (B)

Non-directional string.

Tension is based on buoyed weight.

Neutral point: 8,439 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost ()
1	10100	4.5	11.60	P-110	LT&C	10100	10100	3.875	61933
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	5771	7580	1.31	5771	10694	1.85	98	279	2.85 J

Prepared RJK
by: Utah Dept. of Natural ResourcesDate: October 31, 2000
Salt Lake City, Utah**ENGINEERING STIPULATIONS: NONE**

Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.


Collapse is based on a vertical depth of 10100 ft, a mud weight of 11 ppg. The casing is considered to be evacuated for collapse purposes.

In addition, burst strength is biaxially adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

10-00 Coastal NBU #359

Casing Schematic





State of Utah
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

Michael O. Leavitt
Governor

Kathleen Clarke
Executive Director

Lowell P. Braxton
Division Director

1594 West North Temple, Suite 1210
PO Box 145801
Salt Lake City, Utah 84114-5801
801-538-5340
801-359-3940 (Fax)
801-538-7223 (TDD)

October 31, 2000

Coastal Oil and Gas Corporation
PO Box 1148
Vernal, UT 84078


Re: Natural Buttes Unit 359 Well, 1220' FNL, 2035' FEL, NW NE, Sec. 29, T. 10 South,
R. 21 East, Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-33706.

Sincerely,


John R. Baza
Associate Director

er

Enclosures

cc: Uintah County Assessor
Bureau of Land Management, Vernal Field Office
SITLA

Operator: Coastal Oil and Gas Corporation
Well Name & Number Natural Buttes Unit 359
API Number: 43-047-33706
Lease: ML-21330

Location: NW NE Sec. 29 T. 10 South R. 21 East

Conditions of Approval

1. **General**

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for Permit to Drill.

2. **Notification Requirements**

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- 24 hours prior to cementing or testing casing
- 24 hours prior to testing blowout prevention equipment
- 24 hours prior to spudding the well
- within 24 hours of any emergency changes made to the approved drilling program
- prior to commencing operations to plug and abandon the well

The following are Division of Oil, Gas and Mining contacts and their work telephone numbers (please leave a voice mail message if the person is not available to take the call):

- Dan Jarvis at (801) 538-5338
- Carol Daniels at (801) 538-5284 (spud)

3. **Reporting Requirements**

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. Compliance with the State of Utah Antiquities Act forbids disturbance of archeological, historical, or paleontological remains. Should archeological, historical or paleontological remains be encountered during your operations, you are required to immediately suspend all operations and immediately inform the Trust Lands Administration and the Division of State History of the discovery of such remains.

5. In accordance with Order in Cause No. 190-5(b) dated October 28, 1982, the Operator shall comply with requirements of Rules R649-3-31 and R649-3-27 pertaining to Designated Oil Shale Areas. Additionally, the operator shall ensure that the surface and/or production casing is properly cemented over the entire oil shale interval as defined by Rule R649-3-31. The Operator shall report the actual depth the oil shale is encountered to the Division.

6. Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis. (Copy Attached)

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such purposes

1. Type of Well: OIL ☐ GAS ☒ OTHER:

2. Name of Operator

Coastal Oil & Gas Corporation

3. Address and Telephone Number.

P.O. Box 1148, Vernal UT 84078

(435)781-7023

4. Location of Well

Footages: 1220'FNL & 2035'FEL

QQ,Sec., T., R., M.: NW/NE Sec.29, T10S, R21E

5. Lease Designation and Serial Number

ML-21330

6. Indian, Allottee or Tribe Name:

N/A

7. Unit Agreement Name:

Natural Buttes Unit

8. Well Name and Number:

NBU #359

9. API Well Number:

43-047-33706

10. Field and Pool, or Wildcat

Natural Buttes

County: Uintah

State: UT

11. **CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

NOTICE OF INTENT
(Submit in Duplicate)

- | | |
|--|---|
| <input type="checkbox"/> Abandon | <input type="checkbox"/> New Construction |
| <input type="checkbox"/> Repair Casing | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans | <input type="checkbox"/> Recomplete |
| <input type="checkbox"/> Convert to Injection | <input type="checkbox"/> Perforate |
| <input type="checkbox"/> Fracture Treat or Acidize | <input type="checkbox"/> Vent or Flare |
| <input type="checkbox"/> Multiple Completion | <input type="checkbox"/> Water Shut-Off |
| <input checked="" type="checkbox"/> Other <u>TD Change Wasatch</u> | |

Approximate date work will start _____

SUBSEQUENT REPORT
(Submit Original Form Only)

- | | |
|--|---|
| <input type="checkbox"/> Abandon* | <input type="checkbox"/> New Construction |
| <input type="checkbox"/> Repair Casing | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans | <input type="checkbox"/> Perforate |
| <input type="checkbox"/> Convert to Injection | <input type="checkbox"/> Vent or Flare |
| <input type="checkbox"/> Fracture Treat or Acidize | <input type="checkbox"/> Water Shut-Off |
| <input type="checkbox"/> Other _____ | |

Date of work completion _____

Report results of **Multiple Completions** and **Recompletions** to different reservoirs on WELL COMPLETION OR RECOMPLETION REPORT AND LOG form.

* Must be accompanied by a cement verification report.

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Coastal Oil & Gas Corporation requests authorization to change the TD from 10,100' to 7,200' to the Wasatch formation.

Please refer to the attached Drilling Program.

13. Name & Signature *Cheryl Cameron* Title Sr. Regulatory Analyst Date 12/19/00

(This space for State use only)

Approved by the
Utah Division of
Oil, Gas and Mining

Date: 01-08-01

By: *[Signature]*

(5/94)

COPY SENT TO OPERATOR
Date: 01-09-01
Initials: CHD

(See Instructions on Reverse Side)

RECEIVED

DEC 22 2000

DIVISION OF
OIL, GAS AND MINING

COMPANY NAME	Coastal Oil & Gas Corporation	DATE	12/19/00					
WELL NAME	NBU #359	TD	7,200' MD/TVD					
FIELD	NBU	COUNTY	Uintah	STATE	Utah	ELEVATION	5,210'	KB
SURFACE LOCATION	1,382' FNL & 2,150' FWL Sec 29 T10S-R21E						BHL	Straight Hole
OBJECTIVE ZONE(S)	Wasatch							
ADDITIONAL INFO								

GEOLOGICAL FORMATION			MECHANICAL CASING		
LOGS	TOPS	DEPTH	HOLE SIZE	CASING SIZE	MUD WEIGHT
	(if required)	40'		14"	
			11"	8-5/8", 24#, K-55	Air
		250' MD/TVD			
		Green River @ 1,190'			
			7-7/8"	4-1/2", 11.6#, K-55, LTC	Air Mist Aerated Water
		Wasatch @ 4,270'			
		7,200' MD/TVD			

Mud Log @ 250' - TD

Platform Express

SC - TD

RECEIVED

DEC 22 2000

DIVISION OF
OIL, GAS AND MINING

COASTAL OIL & GAS CORPORATION
DRILLING PROGRAM

CASING PROGRAM

	SIZE	INTERVAL	WT.	GR.	CPLG.	DESIGN FACTORS		
						BURST	COLLAPSE	TENSION
CONDUCTOR	14"	0-40'				2950	1370	263000
SURFACE	8-5/8"	0-250'	24#	K-55	STC	21.03	11.71	4.70
						5350	4960	180000
PRODUCTION*	4-1/2"	0-TD	11.6#	K-55	LTC	2.10	1.32	1.35

- 1) Maximum Anticipated Surface Pressure (MASP) (Conductor and Surface Casings) = (Frac Gradient at Shoe - Gas Gradient (0.115 psi/ft))(TVD)
- 2) MASP (Int Casing) = Pore Pressure at Next Casing Point - (Gas Gradient x TVD of Next Casing Point x 0.67) - (Mud Weight x TVD x 0.052 x 0.33)
- 3) MASP (Prod Casing) = Pore Pressure - (Gas Gradient x TVD of Production Interval)
- (Burst Assumptions: FG @ 8-5/8" shoe = 13.0 ppg, Max Pore Pressure = 9.0 ppg EMW)
- (Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing, 50,000 lbs overpull)

CEMENT PROGRAM


		FT. OF FILL	DESCRIPTION	SACKS	EXCESS*	WEIGHT	YIELD
SURFACE		250	Class G + 2% CaCl ₂ + 0.25 lb/sk Cello Flake	90	35%	15.80	1.17
PRODUCTION	LEAD	4,570'	Premium Lite II + 3 lb/sk CSE + 0.5% Sodium Metasilicate + 10% Gel + 0.25 lb/sk Cello Flake + 3% Salt + 3 lb/sk Kol Seal	600	100%	11.00	3.44
	TAIL	2,630'	50/50 POZ + 0.1% R-3 + 1% EC-1 + 0.2% Sodium Metasilicate + 2% Gel + 0.5% FL-25 + 3% Salt	860	75%	14.5	1.23

* or 15% over caliper log

FLOAT EQUIPMENT & CENTRALIZERS

SURFACE	Guide shoe, 1 jt, float collar. Centralize first 3 joints & every other joint to surface with bow spring centralizers. Thread lock FE up to & including pin end of FC.
PRODUCTION	Guide shoe, 1 jt, float collar. Centralize first 3 joints & every other joint to top of tail cement with bow spring centralizers.

WELLHEAD EQUIPMENT



TREE	2-1/16" 5M
TUBING HEAD	11" 3M X 7-1/16" 5M
CASING SPOOL	
CASING SPOOL	
CASING HEAD	8-5/8" SOW X 11" 3M

RECEIVED
DEC 22 2000
DIVISION OF
OIL, GAS AND MINING

COASTAL OIL & GAS CORPORATION
DRILLING PROGRAM

BIT PROGRAM

ROCK BIT & PDC BIT PROGRAM						
INTERVAL	HOLE	BIT MFG & MODEL	GPM	SERIAL	NZLS	COMMENTS
Surface Hole	11"	Various				
Surf Csg - TD	7-7/8"	SEC XS44	Air/Mist	New	16-16-16	
			Aerated			

If an additional bit is required use another insert.

GEOLOGICAL DATA

LOGGING:

Depth	Log Type
SC - TD	Platform Express

MUD LOGGER:	SC - TD
SAMPLES:	As per Geology
CORING:	NA
DST:	NA

MUD PROGRAM

DEPTH	TYPE	MUD WT	WATER LOSS	VISCOSITY	TREATMENT
0-Trona (0 - +/-2,000')	Air/Mist	NA	NA		Polymer, Gel Gyp, Lime
Trona-TD (+/- 2,000' - TD)	Aerated Water	NA	NC	NA	Polymer, Gyp, Lime

Circulate hole until clean @ TD. Spot brine pill at TD for logs and casing.

ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.
BOPE: 11" 3M with one annular and 2 rams. Test to 3,000 psi (annular to 1,500 psi) prior to drilling out. Record on chart recorder & tour sheet. Function test rams on each trip. Maintain safety valve & inside BOP on rig floor at all times. Kelly to be equipped with upper & lower kelly valves.
Run Totco survey every 1,500' from surface casing shoe to TD. Maximum allowable hole angle is 5 degrees.
Treat for corrosion as per plan.

PROJECT ENGINEER: Christa Yin
PROJECT MANAGER: Darrell Molnar

DIVISION OF
OIL, GAS AND MINING
DATE:
DATE:

RECEIVED
DEC 22 2000

Well name:
 Operator: **Coastal**
 String type: **Production**
 Location: **Uintah County**

01-01 Coastal NBU 359

Project ID:
 43-047-33706

Design parameters:

Collapse

Mud weight: 10.000 ppg
 Design is based on evacuated pipe.

Minimum design factors:

Collapse:

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
 Surface temperature: 65 °F
 Bottom hole temperature: 166 °F
 Temperature gradient: 1.40 °F/100ft
 Minimum section length: 250 ft

Cement top: Surface

Burst

Max anticipated surface pressure: 0 psi
 Internal gradient: 0.519 psi/ft
 Calculated BHP 3,740 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
 8 Round LTC: 1.80 (J)
 Buttress: 1.60 (J)
 Premium: 1.50 (J)
 Body yield: 1.50 (B)

Non-directional string.

Tension is based on air weight.
 Neutral point: 6,124 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost ()
1	7200	4.5	11.60	J-55	LT&C	7200	7200	3.875	24252
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	3740	4960	1.33	3740	5350	1.43	84	162	1.94 J

+ 50 MOP
 134

1.215

Prepared R.A. McKee
 by: Utah Dept. of Natural Resources

Date: January 2, 2001
 Salt Lake City, Utah

ENGINEERING STIPULATIONS: NONE

Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.
 Collapse is based on a vertical depth of 7200 ft, a mud weight of 10 ppg. The casing is considered to be evacuated for collapse purposes.
 Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

Well name:

01-01 Coastal NBU 359

Operator: Coastal

String type: Surface

Project ID:

43-047-33706

Location: Uintah County

Design parameters:**Collapse**

Mud weight: 9.000 ppg

Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No

Surface temperature: 65 °F

Bottom hole temperature: 68 °F

Temperature gradient: 1.40 °F/100ft

Minimum section length: 250 ft

Cement top: Surface

Burst

Max anticipated surface pressure:

0 psi

Internal gradient: 0.468 psi/ft

Calculated BHP 117 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)

8 Round LTC: 1.80 (J)

Buttress: 1.60 (J)

Premium: 1.50 (J)

Body yield: 1.50 (B)

Tension is based on air weight.

Neutral point: 216 ft

Non-directional string.

Re subsequent strings:

Next setting depth: 7,200 ft

Next mud weight: 9.000 ppg

Next setting BHP: 3,366 psi

Fracture mud wt: 19.250 ppg

Fracture depth: 250 ft

Injection pressure 250 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost ()
1	250	8.625	24.00	K-55	ST&C	250	250	7.972	2096
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	117	1370	11.72	117	2950	25.24	6	263	43.83 J

Prepared R.A. McKee
by: Utah Dept. of Natural Resources

Date: January 2,2001
Salt Lake City, Utah

ENGINEERING STIPULATIONS: NONE

Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Collapse is based on a vertical depth of 250 ft, a mud weight of 9 ppg The casing is considered to be evacuated for collapse purposes.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

01-01 Coastal NBU 359

Casing Schematic

HANGE 1

4 1/2" TO 7200'
US. 10,100'

Surface

8-5/8"
MW 9.
Frac 19.3

TOC @
0.

TOC @
0.
Surface
250. MD

10% WAGMOST

23% WAGMOST

$$\begin{aligned} .052 (10) 7200 &= 3744 \\ - .12 (7200) &= \underline{2880 \text{ psi}} \end{aligned}$$

∴ 3M
BOP STW ADEQUATE

4-1/2"
MW 10.

Production
7200. MD

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such purposes

1. Type of Well: OIL ☐ GAS ☒ OTHER:

2. Name of Operator

Coastal Oil & Gas Corporation

3. Address and Telephone Number.

P.O. Box 1148, Vernal UT 84078

(435)781-7023

4. Location of Well

Footages: 1220' FNL & 2035' FEL

QQ, Sec. T., R., M.: NW/NE Sec. 29, T10S, R21E

5. Lease Designation and Serial Number

ML-21330

6. Indian, Allottee or Tribe Name:

N/A

7. Unit Agreement Name:

Natural Buttes Unit

8. Well Name and Number:

NBU #359

9. API Well Number:

43-047-33706

10. Field and Pool, or Wildcat

Natural Buttes

County: Uintah

State: Utah

11. **CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

NOTICE OF INTENT
(Submit in Duplicate)

- | | |
|--|---|
| <input type="checkbox"/> Abandon | <input type="checkbox"/> New Construction |
| <input type="checkbox"/> Repair Casing | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans | <input type="checkbox"/> Recomplete |
| <input type="checkbox"/> Convert to Injection | <input type="checkbox"/> Perforate |
| <input type="checkbox"/> Fracture Treat or Acidize | <input type="checkbox"/> Vent or Flare |
| <input type="checkbox"/> Multiple Completion | <input type="checkbox"/> Water Shut-Off |
| <input type="checkbox"/> Other _____ | |

SUBSEQUENT REPORT
(Submit Original Form Only)

- | | |
|--|---|
| <input type="checkbox"/> Abandon* | <input type="checkbox"/> New Construction |
| <input type="checkbox"/> Repair Casing | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans | <input type="checkbox"/> Perforate |
| <input type="checkbox"/> Convert to Injection | <input type="checkbox"/> Vent or Flare |
| <input type="checkbox"/> Fracture Treat or Acidize | <input type="checkbox"/> Water Shut-Off |
| <input checked="" type="checkbox"/> Other _____ | SPUD |

Date of work completion 12/29/00

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION REPORT AND LOG form.

* Must be accompanied by a cement verification report.

Approximate date work will start _____

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

SPUD well @ 4:00 p.m. w/Bill Jr. Air Rig on 12/29/00

Drilled 260' of 12 1/4" Hole.

RIH 251.55' of 8 5/8" K-55 32# Csg.

Pump 10 Bbls H2O. 30 Bbl Gelled H2O. Followed w/150 SKS Prem Plus @ 15.6 PPG, Yield 1.18 cu. ft/SK
H2O 5.20 gal/SK, 2% Cac12. 125#/SK Poly Flake. Displace w/12.7 Bbl H2O. 11 Bbl Cmt to Pit.

13.

Name & Signature

Cheryl Cameron

Title

Cheryl Cameron

Sr. Regulatory Analyst

Date 1/4/01

(This space for State use only)

RECEIVED

JAN 08 2001

**DIVISION OF
OIL, GAS AND MINING**

ENTITY ACTION FORM - FORM6

ADDRESS P.O. Box 1148


Vernal UT 84078

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		
B	99999	2900	43-047-33706	Natural Buttes Unit #358 357	NW/NE	29	10S	21E	Uintah	12/29/00	12/29/00
WELL 1 COMMENTS:											
1-4-01 Code B: SPUD 4:00 p.m. on 12/29/00 w/Bill Martin Jr. Air Rig											
WELL 2 COMMENTS:											
WELL 3 COMMENTS:											
WELL 4 COMMENTS:											
WELL 5 COMMENTS:											

ACTION CODES (See instructions on back of form)

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected.


Signature Cheryl Cameron
Sr. Regulatory Analyst 1/4/01
Title Date
Phone No. 435 781-7023

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such purposes

1. Type of Well: OIL ☐ GAS ☒ OTHER:

2. Name of Operator

Coastal Oil & Gas Corporation

3. Address and Telephone Number.

P.O. Box 1148, Vernal UT 84078

(435)781-7023

4. Location of Well

Footages: 1220' FNL & 2035' FEL

QQ, Sec., T., R., M.: NW/NE Sec. 29, T10S, R21E

5. Lease Designation and Serial Number

ML-21330

6. Indian, Allottee or Tribe Name:

N/A

7. Unit Agreement Name:

Natural Buttes Unit

8. Well Name and Number:

NBU #359

9. API Well Number:

43-047-33706

10. Field and Pool, or Wildcat

Natural Buttes

County: Uintah

State: Utah

11. **CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

NOTICE OF INTENT
(Submit in Duplicate)

- | | |
|--|---|
| <input type="checkbox"/> Abandon | <input type="checkbox"/> New Construction |
| <input type="checkbox"/> Repair Casing | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans | <input type="checkbox"/> Recomplete |
| <input type="checkbox"/> Convert to Injection | <input type="checkbox"/> Perforate |
| <input type="checkbox"/> Fracture Treat or Acidize | <input type="checkbox"/> Vent or Flare |
| <input type="checkbox"/> Multiple Completion | <input type="checkbox"/> Water Shut-Off |
| <input type="checkbox"/> Other _____ | |

Approximate date work will start _____

SUBSEQUENT REPORT
(Submit Original Form Only)

- | | |
|--|---|
| <input type="checkbox"/> Abandon* | <input type="checkbox"/> New Construction |
| <input type="checkbox"/> Repair Casing | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans | <input type="checkbox"/> Perforate |
| <input type="checkbox"/> Convert to Injection | <input type="checkbox"/> Vent or Flare |
| <input type="checkbox"/> Fracture Treat or Acidize | <input type="checkbox"/> Water Shut-Off |
| <input checked="" type="checkbox"/> Other _____ | Drilling Summary |

Date of work completion 1/11/01

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION REPORT AND LOG form.

* Must be accompanied by a cement verification report.

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Finished Drilling from 260' to 6847'

RIH w/6847' of 4 1/2" 11.6# K-55 LT&C Csg.

Pump 10 Bbls H2O ahead of 30 Bbls SD Spacer followed by 10 Bbl H2O. Lead Slurry 660 SKS

HiFill MOD w/adds @ 11.6#/gal. Yield 3.12 cu.ft/SK 17.80 gal/SK. Tail Slurry 1245 SKS 274 Bbl

50/50 POZ w/adds @ 14.35#/gal. Yield 1.24 cu.ft/SK 5.41 gal/SK. Displace w/106 Bbl H2O.

Bump Plug. Floats Held. Good Circulation. Cmt to Surface. 200 Bbls Cmt to Pit.

Clean Mud Tanks.

Released Rig @ 8:00 a.m. 1/11/01.

13.

Name & Signature

Cheryl Cameron

Title

Cheryl Cameron

Sr. Regulatory Analyst

Date 1/12/01

(This space for State use only)

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such purposes

1. Type of Well: OIL ☐ GAS ☒ OTHER:

2. Name of Operator

Coastal Oil & Gas Corporation

3. Address and Telephone Number.

P.O. Box 1148, Vernal UT 84078

(435)781-7023

4. Location of Well

Footages: 1220'FNL & 2035'FEL

QQ,Sec., T., R., M.: NW/NE Sec.29,T10S,R21E

5. Lease Designation and Serial Number

ML-21330

6. Indian, Allottee or Tribe Name:

N/A

7. Unit Agreement Name:

Natural Buttes Unit

8. Well Name and Number:

NBU #359

9. API Well Number:

43-047-33706

10. Field and Pool, or Wildcat

Natural Buttes

County: Uintah

State: UT

11. **CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

NOTICE OF INTENT
(Submit in Duplicate)

- | | |
|--|---|
| <input type="checkbox"/> Abandon | <input type="checkbox"/> New Construction |
| <input type="checkbox"/> Repair Casing | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans | <input type="checkbox"/> Recomplete |
| <input type="checkbox"/> Convert to Injection | <input type="checkbox"/> Perforate |
| <input type="checkbox"/> Fracture Treat or Acidize | <input type="checkbox"/> Vent or Flare |
| <input type="checkbox"/> Multiple Completion | <input type="checkbox"/> Water Shut-Off |
| <input type="checkbox"/> Other _____ | |

Approximate date work will start _____

SUBSEQUENT REPORT
(Submit Original Form Only)

- | | |
|--|---|
| <input type="checkbox"/> Abandon* | <input type="checkbox"/> New Construction |
| <input type="checkbox"/> Repair Casing | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans | <input type="checkbox"/> Perforate |
| <input type="checkbox"/> Convert to Injection | <input type="checkbox"/> Vent or Flare |
| <input type="checkbox"/> Fracture Treat or Acidize | <input type="checkbox"/> Water Shut-Off |
| <input checked="" type="checkbox"/> Other _____ | Completion Report |

Date of work completion 1/22/01

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION REPORT AND LOG form.

* Must be accompanied by a cement verification report.

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Subject well placed on production on 1/22/01. Please refer to the attached Chronological Well History.

13. Cheryl Cameron

Name & Signature

Title

Sr. Regulatory Analyst

Date 1/25/01

(This space for State use only)

RECEIVED

FEB 05 2001

DIVISION OF
OIL, GAS AND MINING

**THE COASTAL CORPORATION
PRODUCTION REPORT**

CHRONOLOGICAL HISTORY

NBU 359

Page 1

NATURAL BUTTES FIELD
UINTAH COUNTY, UT

WI: 100%

PBTD: 6805' PERFS: 5087' - 6699'

CSG: 4.5", 11.6#, K-55, LT&C @ 6846' 8/8THS AFE MS: 522

SPUD DATE:

FORMATION: WASATCH

CWC(M\$):

AFE DESCRIPTION: DRL & COMP, AFE #: PENDING

01/16/01 PREP TO PICKLE TBG & RUN CBL.
MIRU. RIH W/ 3 7/8" MILL. TAG PBTD @ 6805'.

01/17/01 PREP TO FRAC.
PICKLE TBG. SPOT 7 BBLs 15% HCL ACROSS PERF INTERVAL 6699' - 6239'. RUN CBL, CCL & GR F/ PBTD TO 3900' & 200' BELOW & ABOVE CMT TOP. TO C @ 470'. PERF WASATCH 6693' - 6699', 4 SPF, 24 HOLES. 0 PRESS. BRK DN PERFS W/ 2600# @ 3.5 BPM - ISIP: 2400#, 15 MIN: 700#.

01/18/01 PREP TO DO CBP'S.
STAGE #1 FRAC PERFS 6693' - 6699' W/ 36,000# 20/40 SD W/ PROP NET IN LAST 10% SD & 421 BBLs YF115ST LIQUID/GEL. MTP: 4450#, ATP: 3646#, MTR: 27.3 BPM, ATR: 22.7 BPM. ISIP: 3259#, FG: 0.9, NET PRESS INCR: 850#. RIH W/ CBP & PERF GUN. SET CBP @ 6650'.

STAGE #2 PERF WASATCH 6544' - 6550', 4 SPF, 24 HOLES. BRK DN W/ 4644#. FRAC W/ 34,000# 20/40 SD W/ PROP NET IN LAST 10% SD & 410 BBLs YF115ST LIQUID/GEL. MTP: 4610#, ATP: 3579#, MTR: 24.7 BPM, ATR: 21.4 BPM, ISIP: 3168#, NET PRESS INCR: 1113#. RIH W/ CBP & PERF GUN. SET CBP @ 6490'.

STAGE #3 PERF WASATCH 5514' - 5518', 4 SPF, 16 HOLES & 5506' - 5510', 4 SPF, 16 HOLES. BRK DN PERFS W/ 3186# @ 4.1 BPM - ISIP: 1320#. FRAC W/ 44,800# 20/40 SD W/ PROP NET IN LAST 10% SD. ISIP: 2580#, FG: 0.9, NET PRESS INCR: 1260#. MTP: 3621#, ATP: 2844#, MTR: 31.2 BPM, ATR: 26 BPM. RIH W/ CBP & PERF GUN. SET CBP @ 5447'.

STAGE #4 PERF WASATCH 5288' - 5298', 4 SPF, 40 HOLES. BRK DN PERFS W/ 2128# @ 4.2 BPM - ISIP: 1100#. FRAC W/ 39,000# 20/40 SD W/ PROP NET IN LAST 10% SD. ISIP: 2345#, FG: 0.88, NET PRESS INCR: 1245#, MTP: 2770#, ATP: 2433#, MTR: 25.7 BPM, ATR: 23.1 BPM. RIH W/ CBP & PERF GUN. SET CBP @ 5220'.

STAGE #5 PERF WASATCH 5089' - 5091', 4 SPF, 8 HOLES & 5078' - 5084', 4 SPF, 24 HOLES. BRK DN W/ 2439# @ 4.5 BPM - ISIP: 845#. FRAC W/ 42,000# 20/40 SD W/ 10% PROP NET IN LAST 10% SD & 449 BBLs YF115ST LIQUID/GEL. ISIP: 2258#, FG: 0.87, NET PRESS INCR: 1413#, MTP: 2724#, ATP: 2352#, MTR: 30.2 BPM, ATR: 27.9 BPM. RIH & SET CBP @ 5010'. TLTR: 2208 BBLs.

01/19/01 PREP TO DO LAST CBP & FLOW BACK.
RIH & DO CBP'S @ 5010', 5220', 5447' & 6490' W/ 3% KCL WTR. FLOW BACK 12 HRS ON FULL OPEN CHK. FTP: 40# TO 75#, CP: 50# TO 100#, 71 BWPH TO 15 BWPH, TLTR: 2208 BBLs, TLR: 839 BBLs, LLTR: 369 BBLs.

01/20/01 PREP TO SWAB.
RIH & DO CBP @ 6650'. CO TO PBTD W/ AIR FOAM. PU & LAND TBG @ 6675', SN @ 6624'. RDMO. WELL DEAD.

01/21/01 FLOW TESTING.
SITP: 0#, SICP: 1750#. SWAB WELL IN. IFL @ SURF, FFL @ 500'. REC 175 BLW. FLOW BACK 13 HRS ON 32/64" CHK, FTP: 200# TO 300#, CP: 1250# TO 1200#, 33 BWPH TO 27 BWPH, REC 401 BLW, LLTR: 489 BBLs.

01/22/01 PREP TO PLACE ON SALES.
FLOW BACK 24 HRS ON 32/64" CHK, FTP: 300#, CP: 1100#, 500 MCFPD, 27 BWPH TO 10

BWPH, REC 555 BLW (66 BBLs OVERLOAD).

01/23/01 **PROG: PLACED ON SALES @ 8:10 AM, 1/22/01. SPOT PROD DATA: CHK: 34/64",**
FTP: 400#, CP: 900#, 400 BWPD, 600 MCFPD, LP: 293#.

01/24/01 **PROG: FLWD 595 MCF, 185 BW, FTP: 360#, CP: 570#, 37/64" CHK, 24 HRS, LP: 303#.**

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

WELL COMPLETION OR RECOMPLETION REPORT AND LOG*

1a. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> DRY <input type="checkbox"/> Other _____ 1b. TYPE OF COMPLETION NEW WELL <input checked="" type="checkbox"/> WORK OVER <input type="checkbox"/> DEEP EN <input type="checkbox"/> PLUG BACK <input type="checkbox"/> DIFF. RESVR. <input type="checkbox"/> Other _____						5. LEASE DESIGNATION AND SERIAL NO. ML-21330	
						6. IF INDIAN, ALLOTTEE OR TRIBE NAME N/A	
						7. UNIT AGREEMENT NAME Natural Buttes Unit	
2. NAME OF OPERATOR Coastal Oil & Gas Corporation						8. FARM OR LEASE NAME Natural Buttes Unit	
3. ADDRESS AND TELEPHONE NO. P.O. Box 1148 Vernal, UT 84078 435) 781-7023						9. WELL NO. 359	
4. LOCATION OF WELL (Report locations clearly and in accordance with any State requirements) At Surface NW/NE 1220' FNL & 2035' FEL At top prod. Interval reported below same At total depth same						10. FIELD AND POOL OR WILDCAT Natural Buttes	
14. API NO. 43-047-33706 DATE ISSUED 10/31/2000						12. COUNTY Uintah	
15. DATE SPURRED 12/29/00 16. DATE T.D. REACHED 01/11/01 17. DATE COMPL. (Ready to prod. or Plug & 18. ELEVATIONS (DF, RKB, RT, GR, ETC.)* 5196.2' GR						13. STATE UTAH	
20. TOTAL DEPTH, MD & TVD 6847' MD 6808' TVD						19. ELEV. CASINGHEAD	
21. PLUG, BACK T.D., MD & TVD TD 6808' MD 6808' TVD						22. IF MULTIPLE COMPL., HOW MANY	
23. INTERVALS ROTARY TOOLS DRILLED BY -----> X						24. PRODUCING INTERVAL(S), OF THIS COMPLETION--TOP, BOTTOM, NAME (MD AND TVD) Wasatch 5078'-6699'	
25. WAS DIRECTIONAL SURVEY MADE No							
26. TYPE ELECTRIC AND OTHER LOGS RUN CN/BL/CO/GR-1-22-01 Q/L/GR-122-01 CBL, CCL, GR-1-16-01 +1-23-01						27. WAS WELL CORED YES <input type="checkbox"/> NO <input checked="" type="checkbox"/> (Submit analysis) DRILL STEM TEST YES <input type="checkbox"/> NO <input checked="" type="checkbox"/> (See reverse side)	
23. CASING RECORD (Report all strings set in well)							
CASING SIZE		WEIGHT, LB./FT.		DEPTH SET (MD)		HOLE SIZE	
8 5/8" K-55		32#		252'		12 1/4"	
4.5" K-55		11.6#		6846'		7 7/8"	
29. LINER RECORD				30. TUBING RECORD			
SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT*	SCREEN (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
					2 3/8"	6675'	
31. PERFORATION RECORD (Interval, size and number)				32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.			
INTERVAL	SIZE	NUMBER	EPTH INTERVAL(M) AMOUNT AND KIND OF MATERIAL USED				
6693'-6699'	3 3/8"	24	6693'-6699' w/36,000# 20/40 sd w/10% prop-net & 421 BBLS YF115ST				
6544'-6550'	3 3/8"	24	6544'-6550' w/34,000# 20/40 sd w/10% prop-net & 410 BBLS YF115ST				
5514'-5518'	3 3/8"	16	5506'-5518' w/44,800# 20/40 sd w/10% prop-net & 484 BBLS YF115ST				
5506'-5510'	3 3/8"	16	5288'-5298' w/39,000# 20/40 sd w/10% prop-net & 434 BBLS YF115ST				
5288'-5298'	3 3/8"	40	5078'-5091' w/42,000# 20/40 sd w/10% prop-net & 449 BBLS YF115ST				
5089'-5091'	3 3/8"	8					
5078'-5084'	3 3/8"	24					
33.* PRODUCTION							
DATE FIRST PRODUCTION 01/22/01		PRODUCTION METHOD (Flowing, gas lift, pumping--size and type of pump) Flowing				WELL STATUS (Producing or shut-in) Producing	
DATE OF TEST 01/24/01	HOURS TESTED 24	CHOKE SIZE 40/64"	PROD'N. FOR TEST PERIOD ----->	OIL--BBLS. 0	GAS--MCF. 670	WATER--BBL. 200	GAS-OIL RATIO 200
FLOW. TUBING PRESS. 375#	CASING PRESSURE 860#	CALCULATED 24-HOUR RATE ----->	OIL-BBL. 0	GAS--MCF. 670	WATER--BBL. 200	OIL GRAVITY-API (CORR.) FEB 12 2001	
34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.) Sold, used for fuel						TEST WITNESSED BY DIVISION OF OIL, GAS AND MINING	
35. LIST OF ATTACHMENTS							

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records

SIGNED Cheryl Cameron TITLE Senior Regulatory Analyst DATE 1/31/01
 Cheryl Cameron

See Spaces for Addition Data on Reverse Side

INSTRUCTIONS

This form should be completed in compliance with the Utah Oil and Gas Conservation General Rules. If not filed prior to this time, all logs, tests, and directional surveys as required by Utah Rules should be attached and submitted with this report.

ITEM 18: Indicate which elevation is used as reference for depth measurements given in other spaces on this form and on any attachments. ITEMS 22 and 24: If this well is completed for separate production from more than one interval zone (multiple completion), so state in item 22, and in item 24 show the producing interval, or intervals, top(s), bottom(s) and name(s) for only the interval reported in item 33. Submit a separate report (page) on this form, adequately identified, for each additional interval to be separately produced, showing the additional data pertinent to such interval.

ITEM 29: "Sacks Cement": Attached supplemental records for this well should show the details of any multiple stage cementing and the location of the cementing tool.

ITEM 33: Submit a separate completion report on this form for each interval to be separately produced (see instruction for items 22 and 24 above).

37. SUMMARY OF POROUS ZONES: Show all important zones of porosity and contents thereof; cored intervals; and all drill-stem, tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.		38. GEOLOGIC MARKERS				
Formation	Top	Bottom	Description, contents, etc.	Name	Meas. Depth	Top True Vert. Depth
				Green River Wasatch	1065' 4222'	

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL ☐ GAS WELL ☐ OTHER ☐

2. NAME OF OPERATOR:
El Paso Production Oil & Gas Company

3. ADDRESS OF OPERATOR: 58 South 1200 East CITY Vernal STATE Utah ZIP 84078 PHONE NUMBER: 435-789-4433

4. LOCATION OF WELL

FOOTAGES AT SURFACE:

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:

5. LEASE DESIGNATION AND SERIAL NUMBER:

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:

8. WELL NAME and NUMBER:

Exhibit "A"

9. API NUMBER:

10. FIELD AND POOL, OR WILDCAT:

COUNTY:

STATE:

UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input type="checkbox"/> PRODUCTION (START/RESUME) <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	<input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TEMPORARILY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUT-OFF <input checked="" type="checkbox"/> OTHER: Name Change
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

As a result of the merger between The Coastal Corporation and a wholly owned subsidiary of El Paso Energy Corporation, the name of Coastal Oil & Gas Corporation has been changed to El Paso Production Oil & Gas Company effective March 9, 2001.

See Exhibit "A"

Bond # 400JU0708

Coastal Oil & Gas Corporation

NAME (PLEASE PRINT) John T. Elzner

TITLE Vice President

SIGNATURE [Signature]

DATE 06-15-01

El Paso Production Oil & Gas Company

NAME (PLEASE PRINT) John T. Elzner

TITLE Vice President

SIGNATURE [Signature]

DATE 06-15-01

(This space for State use only)

RECEIVED

JUN 19 2001

DIVISION OF
OIL, GAS AND MINING

State of Delaware
Office of the Secretary of State

PAGE 1

I, HARRIET SMITH WINDSOR, SECRETARY OF STATE OF THE STATE OF DELAWARE, DO HEREBY CERTIFY THE ATTACHED IS A TRUE AND CORRECT COPY OF THE CERTIFICATE OF AMENDMENT OF "COASTAL OIL & GAS CORPORATION", CHANGING ITS NAME FROM "COASTAL OIL & GAS CORPORATION" TO "EL PASO PRODUCTION OIL & GAS COMPANY", FILED IN THIS OFFICE ON THE NINTH DAY OF MARCH, A.D. 2001, AT 11 O'CLOCK A.M.

RECEIVED

JUN 14 2001

DIVISION OF
OIL, GAS AND MINING



Harriet Smith Windsor
Harriet Smith Windsor, Secretary of State

0610204 8100

AUTHENTICATION: 1061007

010162788

DATE: 04-03-01

CERTIFICATE OF AMENDMENT

OF

CERTIFICATE OF INCORPORATION

COASTAL OIL & GAS CORPORATION (the "Company"), a corporation organized and existing under and by virtue of the General Corporation Law of the State of Delaware, DOES HEREBY CERTIFY:

FIRST: That the Board of Directors of the Company, by the unanimous written consent of its members, filed with the minutes of the Board, adopted a resolution proposing and declaring advisable the following amendment to the Certificate of Incorporation of the Company:

RESOLVED that it is deemed advisable that the Certificate of Incorporation of this Company be amended, and that said Certificate of Incorporation be so amended, by changing the Article thereof numbered "FIRST," so that, as amended, said Article shall be and read as follows:

"FIRST. The name of the corporation is El Paso Production Oil & Gas Company."

SECOND: That in lieu of a meeting and vote of stockholders, the stockholders entitled to vote have given unanimous written consent to said amendment in accordance with the provisions of Section 228 of the General Corporation Law of the State of Delaware.

THIRD: That the aforesaid amendment was duly adopted in accordance with the applicable provisions of Sections 242 and 228 of the General Corporation Law of the State of Delaware.

IN WITNESS WHEREOF, said COASTAL OIL & GAS CORPORATION has caused this certificate to be signed on its behalf by a Vice President and attested by an Assistant Secretary, this 9th day of March 2001.

COASTAL OIL & GAS CORPORATION



David L. Siddall
Vice President

Attest:


Margaret E. Roark, Assistant Secretary

RECEIVED

STATE OF DELAWARE
SECRETARY OF STATE
DIVISION OF CORPORATIONS
FILED 11:00 AM 03/09/2001
010118394 - 0610204

JUN 19 2001

DIVISION OF
OIL, GAS AND MINING



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155

RECEIVED

JUL 12 2001

DIVISION OF
OIL, GAS AND MINING

In Reply Refer To:
3106
UTSL-065841
(UT-924)

JUL 10 2001

NOTICE

El Paso Production Oil & Gas Company	:	Oil and Gas
Nine Greenway Plaza	:	
Houston TX 77046-0095	:	

Name Change Recognized


Acceptable evidence has been received in this office concerning the name change of Coastal Oil & Gas Corporation into El Paso Production Oil & Gas Company with El Paso Production Oil & Gas Company being the surviving entity.

For our purposes, the name change is recognized effective March 9, 2001.

The oil and gas lease files identified on the enclosed exhibit have been noted as to the name change. The exhibit was compiled from a list of leases obtained from our computer program. We have not abstracted the lease files to determine if the entities affected by this name change hold an interest in the leases identified nor have we attempted to identify leases where the entities are the operator on the ground maintaining no vested recorded title or operating rights interests. We will be notifying the Minerals Management Service and all applicable Bureau of Land Management offices of the change by a copy of this notice. If additional documentation for changes of operator are required by our Field Offices, you will be contacted by them.

If you identify additional leases in which the entities maintain an interest, please contact this office and we will appropriately document those files with a copy of this Notice.

Due to the name change, the name of the principal/obligor on the bond is required to be changed from Coastal Oil & Gas Corporation to El Paso Production Oil & Gas Company. You may accomplish this either by consent of surety rider on the original bond or a rider to the original bond. The bonds are held in Wyoming and Colorado.



Opolonia L. Abeyta
Acting Chief, Branch of
Minerals Adjudication

Enclosure

1. Exhibit of Leases (1 pp)

cc: Moab Field Office
Vernal Field Office
MMS, Reference Data Branch, MS3130, PO Box 5860, Denver CO 80217
State of Utah, DOGM, Attn: Jim Thompson (Ste. 1210), Box 145801, SLC UT 84114
Teresa Thompson (UT-922)
Joe Incardine (UT-921)

Exhibit of Leases

UTUSL-065841A	UTU-47172	UTU-74415	UTU-53860
UTU-28652	UTU-50687	UTU-74416	UTU-66401
UTU-37943	UTU-52298	UTU-75091	UTU-67868
UTU-44089	UTU-0109054	UTU-75096	UTU-65389
UTU-44090A	UTU-0143511	UTU-75097	UTU-77084
UTU-61263	UTU-0143512	UTU-75673	UTU-61430
UTU-00343	UTU-38401	UTU-76259	UTU-72633
UTU-02651	UTU-38411	UTU-76260	UTU-72650
UTU-02651B	UTU-38418	UTU-76261	UTU-49692
UTU-0142175	UTU-38419	UTU-76493	UTU-57894
UTU-70235	UTU-38420	UTU-76495	UTU-76829
UTU-70406	UTU-38421	UTU-76503	UTU-76830
UTU-74954	UTU-38423	UTU-78228	UTU-76831
UTU-75132	UTU-38424	UTU-78714	
UTU-75699	UTU-38425	UTU-78727	
UTU-76242	UTU-38426	UTU-78734	
UTU-78032	UTU-38427	UTU-79012	
UTU-4377	UTU-38428	UTU-79011	
UTU-4378	UTU-53861	UTU-71694	
UTU-7386	UTU-58097	UTU-00576	
UTU-8344A	UTU-64376	UTU-00647	
UTU-8345	UTU-65222	UTU-01470D	
UTU-8347	UTU-65223	UTU-0136484	
UTU-8621	UTU-66746	UTU-8344	
UTU-14646	UTU-67178	UTU-8346	
UTU-15855	UTU-67549	UTU-8648	
UTU-25880	UTU-72028	UTU-28212	
UTU-28213	UTU-72632	UTU-30289	
UTU-29535	UTU-73009	UTU-31260	
UTU-29797	UTU-73010	UTU-33433	
UTU-31736	UTU-73013	UTU-34711	
UTU-34350	UTU-73175	UTU-46699	
UTU-34705	UTU-73434	UTU-78852	
UTU-37116	UTU-73435	UTU-78853	
UTU-37355	UTU-73444	UTU-78854	
UTU-37573	UTU-73450	UTU-075939	
UTU-38261	UTU-73900	UTU-0149767	
UTU-39223	UTU-74409	UTU-2078	
UTU-40729	UTU-74410	UTU-44426	
UTU-40736	UTU-74413	UTU-49530	
UTU-42469	UTU-74414	UTU-51026	

OPERATOR CHANGE WORKSHEET

ROUTING

1. GLH		4-KAS
2. CDW ✓		5-LP ✓
3. JLT		6-FILE

Enter date after each listed item is completed

Change of Operator (Well Sold)

Designation of Agent

Operator Name Change (Only)

X Merger

The operator of the well(s) listed below has changed, effective: **3-09-2001**

FROM: (Old Operator):
COASTAL OIL & GAS CORPORATION
Address: 9 GREENWAY PLAZA STE 2721
HOUSTON, TX 77046-0995
Phone: 1-(713)-418-4635
Account N0230

TO: (New Operator):
EL PASO PRODUCTION OIL & GAS COMPANY
Address: 9 GREENWAY PLAZA STE 2721 RM 2975B
HOUSTON, TX 77046-0995
Phone: 1-(832)-676-4721
Account N1845

CA No.

Unit: NATURAL BUTTES

WELL(S)

NAME	API NO	ENTITY NO	SEC TWN RNG	LEASE TYPE	WELL TYPE	WELL STATUS
NBU 379-2E	43-047-33782	2900	02-09S-21E	STATE	GW	P
NBU 104	43-047-31957	2900	16-09S-21E	STATE	GW	P
NBU 424-32E	43-047-33699	2900	32-09S-21E	STATE	GW	P
NBU SWD 2-16	43-047-33597	13196	16-10S-21E	STATE	WD	DRL
NBU 359	43-047-33706	2900	29-10S-21E	STATE	GW	P
NBU 38	43-047-30536	2900	13-10S-22E	STATE	GW	P
NBU CIGE 43-14-10-22	43-047-30491	2900	14-10S-22E	STATE	GW	P
NBU 361	43-047-33705	2900	32-10S-22E	STATE	GW	P
CIGE 222-36-9-22	43-047-32869	2900	36-09S-22E	STATE	GW	P

OPERATOR CHANGES DOCUMENTATION

- (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 06/19/2001
- (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 06/19/2001
- The new company has been checked through the **Department of Commerce, Division of Corporations Database** on: 06/21/2001
- Is the new operator registered in the State of Utah: YES Business Number: 608186-0143
- If **NO**, the operator was contacted on: N/A

6. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the (merger, name change, or operator change for all wells listed on Federal or Indian leases on: 07/10/2001
7. **Federal and Indian Units:** The BLM or BIA has approved the successor of unit operator for wells listed on: 07/10/2001
8. **Federal and Indian Communization Agreements ("CA"):** The BLM or the BIA has approved the operator change for all wells listed involved in a CA on: N/A
9. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: N/A

DATA ENTRY:

1. Changes entered in the **Oil and Gas Database** on: 07/20/2001
2. Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 07/20/2001
3. Bond information entered in RBDMS on: N/A
4. Fee wells attached to bond in RBDMS on: N/A

STATE BOND VERIFICATION:

1. State well(s) covered by Bond No.: 400JU0705

FEDERAL BOND VERIFICATION:

1. Federal well(s) covered by Bond No.: N/A

FEE WELLS - BOND VERIFICATION/LEASE INTEREST OWNER NOTIFICATION:

1. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond No: N/A
2. The **FORMER** operator has requested a release of liability from their bond on: N/A
The Division sent response by letter on: N/A
3. (R649-2-10) The **FORMER** operator of the Fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: _____

FILMING:

1. All attachments to this form have been **MICROFILMED** on: _____

FILING:

1. **ORIGINALS/COPIES** of all attachments pertaining to each individual well have been filled in each well file on: _____

COMMENTS: Master list of all wells involved in operator change from Coastal Oil & Gas Corporation to El Paso Production Oil and Gas Company shall be retained in the "Operator Change File".

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.
 Use APPLICATION FOR PERMIT -- for such proposals

6. Lease Designation and Serial Number

ML-21330

7. Indian Allottee or Tribe Name

8. Unit or Communitization Agreement

9. Well Name and Number

NBU #359

10. API Well Number

43-047-33706

11. Field and Pool, or Wildcat

NATURAL BUTTES FIELD

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other (specify)

2. Name of Operator

COASTAL OIL & GAS CORPORATION

3. Address of Operator

1368 SOUTH 1200 EAST VERNAL, UT 84078

4. Telephone Number

(435)-781-7023

5. Location of Well

Footage : 1220'FNL & 2035'FEL

County : UINTAH

OO, Sec. T., R., M. : NWNE SECTION 29-T10S-R21E

State : UTAH

12. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

NOTICE OF INTENT

(Submit in Duplicate)

<input type="checkbox"/> Abandonment	<input type="checkbox"/> New Construction
<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Pull or Alter Casing
<input type="checkbox"/> Change of Plans	<input type="checkbox"/> Recompletion
<input type="checkbox"/> Conversion to Injection	<input type="checkbox"/> Shoot or Acidize
<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Vent or Flare
<input type="checkbox"/> Multiple Completion	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Other _____	

Approximate Date Work Will Start _____

SUBSEQUENT REPORT

(Submit Original Form Only)

<input type="checkbox"/> Abandonment *	<input type="checkbox"/> New Construction
<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Pull or Alter Casing
<input type="checkbox"/> Change of Plans	<input type="checkbox"/> Shoot or Acidize
<input type="checkbox"/> Conversion to Injection	<input type="checkbox"/> Vent or Flare
<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Other <u>SQUEEZE TWO WASATCH ZONES</u>	

Date of Work Completion 4/11/01

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION AND LOG form.

* Must be accompanied by a cement verification report.

13. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

THE SUBJECT WELL WAS PLACED BACK ON PRODUCTION ON 4/11/01.
 PLEASE REFER TO THE ATTACHED CHRONOLOGICAL WELL HISTORY.

RECEIVED

MAY 02 2001

DIVISION OF
OIL, GAS AND MINING

14. I hereby certify that the foregoing is true and correct.

Name & Signature CHERYL CAMERON *Cheryl Cameron* Title Sr. Regulatory Analyst Date 04/30/01

(State Use Only)

THE COASTAL CORPORATION
PRODUCTION REPORT
CHRONOLOGICAL HISTORY

NBU 359

LOC: NWNE SEC. 29, T10S, R21E
NATURAL BUTTES FIELD
UINTAH COUNTY, UT

Page 1

WI: 100%

PBTD: 6805' PERFS: 5087' - 6699'

CSG: 4 1/2", 11.6#, K-55 LT&C @ 6846' 8/8THS AFE MS:57

FORMATION: WASATCH

CWC(M\$):

AFE DESCRIPTION: SQUEEZE & TEST ISOLATE MIDDLE 2 ZONES, AFE #: 052335

3/27/01

PREP TO POOH W/TBG

PROG: MI. TOO WINDY TO RIG UP.

3/28/01

PREP TO RIH W/PKR

PROG: SITP: 200#, SICP: 1500#. NUBOPE. RLS PKR @ 6432'. POOH. PKR NOT PULLED. ON/OFF TOOL CAME APART. RIH W/OS. LATCH PKR. SOH W/PKR EOT @ 3905'.

3/29/01

PREP TO SQZ

PROG: POOH & LD PKR. RIH & SET CBP @ 6490'. RIH W.4 1/2" PKR. SET PKR @ 5244'. MADE 3 SWAB TRIPS & WELL STARTED TO FLOW. FTP: 75#, FLWG 60 BWPH. RLS PKR & POOH.

3/30/01

WOC

PROG: RIH & SET CICR @ 5432'. ESTABLISH INJ RATE OF 1.5 BPM @ 1000#. PMP 25 SXS CMT. ISIP: 1200#. POOH W/TBG. RIH W/2ND CICR & SET @ 5272'. ESTABLISH INJ RATE OF 2.6 BPM @ 890#. PMP 25 SXS CMT. ISIP: 40#. RLS FROM CICR. WAIT 2 HRS. STING BACK INTO CICR. INJECT 2 BPM @ 475#. PMP 30 SXS CL "G" CMT. SQZ TO 900#. RLS FROM CICR. PULL ABOVE PERFS.

4/2/01

PREP TO DO CMT

3/31/01 PROG: EST INF RATE INTO PERFS 5089'-509' AND 5078'-5084' @ 2.5 BPM @ 525#. SPOT 70 SXS CL "G" CMT ACROSS PERFS. POOH TO 4235'. SZQ PERFS TO 980#. SIFWE.

4/3/01

PREP TO DO CICR'S

PROG: POOH W/TBG. PU & RIH W/3 7/8" DRL BIT. TAG CMT @ 5055'. DO CMT TO 5110'. FELL THROUGH. CO WELLBORE TO 5140'. PRESS TST SQZ TO 1000#. HELD. RIH & TAG CMT TOP @ 5240'. DO CMT TO CICR @ 5250'. DRL ON CICR 3 1/2 HRS. SIFD.

4/4/01

PREP TO RE-SQZ

PROG: DO CMT RET @ 5250'. DO CMT TO 5303' & FELL THROUGH. CO TO 5360'. PRESS TST CSG TO 1000#. PRESS DROP TO 0 IN 45 SECONDS. EST INJ RATE OF 1 BPM @ 600#. POOH W/BIT. RIH OPEN ENDED. EOT @ 5200'.

4/5/01

WOC

PROG: FILL HOLE. PRESS TST TO 1500#. BLED OFF TO 700# IN 5 MIN. MADE 18 SWAB TRIPS. RECOVER 80 BF. FFL @ 4600' & STAYED CONSTANT FOR LAST 4 TRIPS. EST INJ RATE OF 0.5 BPM @ 1500#. SPOT 10 SXS CMT ACROSS PERFS. SQZ PERFS TO 1025#.

4/6/01

PREP TO DO CMT

PROG: SI WOC.

4/9/01

PREP TO DO CMT RET

4/7/01 PROG: RIH & TAG CMT @ 4979'. DO CMT STRINGERS TO 5190'. DO HARD CMT TO 5205'. PRESS TST PERFS TO 1000#. HELD. RIH & TAG CMT ON THIRD ZONE @ 5440'. DO CMT TO CICR @ 5450'. DRL ON CMT RET 3 HRS. PU TO 5011'. SDFWE.

4/10/01

PREP TO DO CMT

PROG: DO CMT RET (4 HRS). FELL THROUGH. DO CMT TO 5510'. CIRC WELL CLEAN. EOT @ 5480'.

4/11/01

DRILL CBP

PROG: RIH & TAGG CMT @ 5497'. DRILLED CMT FROM 5497' 5522'. CIRC WELL CLEAN & PRESS TESTED TO 1000# OKAY. POOH. RIH W/NEW 3 7/8" BIT, PUMP OFF SUB & +45SN ON 2 3/8" TBG. TAGGED CBP @ 6494'.

4/12/01

PREP TO RETURN TO SALES

PROG: RIH & DO CBP @ 6500'. RIH TO PBTD @ 6803'. PU & LAND TBG @ 6599', SN @ 6567'. PUMP OFF BIT SUB. OPEN WELL TO FBT ON 24/64" CHK. FLOW BACK 13 HRS ON 18/64" CHK. FTP: 50# TO 5#, CP: 240# TO 300#, 3 BWPH TO 0. TLTR: 682 BBLs, TLR: 230 BBLs, LLTR: 452 BBLs.

4/16/01

RETURN TO SALES

4/13/01 PROG: BUILDING PRESS. UNABLE TO BUCK LINE PRESS OF 300#.

4/14/01 PROG: SI TO BUILD PRESS.

4/15/01 PROG: 87 MCF, 0 BC, 11 BW, FTP: 295#, CP: 553#, 64/64" CHK, 24 HRS, LP: 294#.

4/16/01 PROG: 35 MCF, 0 BC, 7 BW, FTP: 318#, CP: 511#, 64/64 CHK, 21 HRS, LP: 317#.

4/17/01

RETURN TO SALES

PROG: 31 MCF, 0 BC, 5 BW, FTP: 292#, CP: 557#, CHK: 64/64", 24 HRS. LP: 292#.

4/18/01

RETURN TO SALES

PROG: 77 MCF, 0 BC, 12 BW, TP: 94#, CP: 395#, CHK: 64/64", 24 HRS. LP: 72#.

4/19/01

RETURN TO SALES

PROG: 80 MCF, 0 BC, 8 BW, TP: 68#, CP: 334#, CHK: 64/64", 24 HRS. LP: 68#. **FINAL REPORT.**

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB NO. 1004-0135
Expires: November 30, 2000

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.

5. Lease Serial No.
ML-21330

6. If Indian, Allottee or Tribe Name
N/A

7. If Unit or CA/Agreement, Name and/or No.
NBU

8. Well Name and No.
NBU 359

API Well No.
43-047-33706

10. Field and Pool, or Exploratory
NATURAL BUTTES

11. County or Parish, and State
UINTAH COUNTY, UT

SUBMIT IN TRIPLICATE - Other instructions on reverse side.

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator
EL PASO PRODUCTION

Contact: CHERYL CAMERON
E-Mail: Cheryl.Cameron@CoastalCorp.com

3a. Address
P.O. BOX 1148
VERNAL, UT 84078

3b. Phone No. (include area code)
Ph: 435.781.7023
Fx: 435.789.4436

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
Sec 29 T10S R21E Mer NWNE 1220FNL 2035FEL

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input checked="" type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

Any produced water from the subject well will be contained in a water tank and will be hauled by truck to one of the pre-approved disposal sites: RNI, Sec.5, T9S, R22E, NBU #159, Sec.35, T9S, R21E, Ace Oilfield, Sec.2, T6S, R20E, MC&MC, Sec.12, T6S, R19E.

**Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY**

RECEIVED

SEP 04 2001

**DIVISION OF
OIL, GAS AND MINING**

14. I hereby certify that the foregoing is true and correct.

**Electronic Submission #6835 verified by the BLM Well Information System
For EL PASO PRODUCTION, sent to the Vernal**

Name (Printed/Typed) CHERYL CAMERON

Title OPERATIONS

Signature

Date 08/29/2001

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved By

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ****

JAN. 17. 2003 3:34PM

WESTPORT

NO. 173 P. 2

**WESTPORT OIL AND GAS COMPANY, L.P.**

410 Seventeenth Street #2300 Denver Colorado 80202-4436
Telephone: 303 573 5404 Fax: 303 573 5609

February 1, 2002

Department of the Interior
Bureau of Land Management
2850 Youngfield Street
Lakewood, CO 80215-7093
Attention: Ms. Martha Maxwell

RE: BLM Bond CO-1203
BLM Nationwide Bond 158626364
Surety - Continental Casualty Company
Belco Energy Corporation merger into Westport Oil and Gas Company, Inc.
Conversion of Westport Oil and Gas Company, Inc., into Westport Oil and Gas Company, L.P.
Assumption Rider - Westport Oil and Gas Company, L.P.

Dear Ms. Maxwell:

Pursuant to our recent conversations, please find the following list of enclosures for the BLM's consideration and approval:

Two (2) Assumption Riders, fully executed originals.
Copies of Belco Energy Corporation merger into Westport Oil and Gas Company, Inc.
Copies of Westport Oil and Gas Company, Inc., conversion into Westport Oil and Gas Company, L.P.
List of all Federal/BIA/State Leases - Belco/Westport's leases - in all states.

Please inform us of any additional information needed to complete the change to Westport Oil and Gas Company, L.P., as operator of record.

I thank you for your assistance and cooperation in this matter. Please do not hesitate contacting the undersigned, should a question arise.

Sincerely,
Westport Oil and Gas Company, L.P.

Debby J. Black
Engineer Technician

Encl;



United States Department of the Interior **RECEIVED**

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155

FEB 22 2002

DIVISION OF
OIL, GAS AND MINING

In Reply Refer To:

3106

UTU-25566 et al

(UT-924)

FEB 21 2002

NOTICE

Westport Oil and Gas Company L.P. : Oil and Gas
410 Seventeenth Street, #2300 :
Denver Colorado 80215-7093 :

Name Change Recognized

Acceptable evidence has been received in this office concerning the name change of Westport Oil and Gas Company, Inc. into Westport Oil and Gas Company, L.P. with Westport Oil and Gas Company, L.P. being the surviving entity.


For our purposes, the name change is recognized effective December 31, 2001.

The oil and gas lease files identified have been noted as to the name change. The exhibit was compiled from a list of leases obtained from our computer program. We have not abstracted the lease files to determine if the entities affected by this name change hold an interest in the leases identified nor have we attempted to identify leases where the entities are the operator on the ground maintaining no vested recorded title or operating rights interests. We will be notifying the Minerals Management Service and all applicable Bureau of Land Management offices of the change by a copy of this notice. If additional documentation for changes of operator are required by our Field Offices, you will be contacted by them.

If you identify additional leases in which the entities maintain an interest, please contact this office and we will appropriately document those files with a copy of this Notice.

Due to the name change, the name of the principal/obligor on the bond is required to be changed from Westport Oil and Gas Company, Inc. to Westport Oil and Gas Company, L.P.. You may accomplish this either by consent of surety rider on the original bond or a rider to the original bond. The bonds are held in Colorado.

UTU-03405
UTU-20895
UTU-25566
UTU-43156
UTU-49518
UTU-49519
UTU-49522
UTU-49523



Robert Lopez
Chief, Branch of
Minerals Adjudication

cc: Moab Field Office
Vernal Field Office
MMS, Reference Data Branch, MS3130, PO Box 5860, Denver CO 80217
State of Utah, DOGM, Attn: Jim Thompson (Ste. 1210), Box 145801, SLC UT 84114
Teresa Thompson (UT-922)
Joe Incardine (UT-921)

memorandum

Branch of Real Estate Services
Uintah & Ouray Agency

Date: 5 December, 2002

Reply to
Attn of: Supervisory Petroleum Engineer

Subject: Modification of Utah Division of Oil, Gas and Mining Regulations

To: Director, Utah Division of Oil, Gas and Mining Division: John Baza

We have been advised of changes occurring with the operation of your database for Change of Operator. You will be modifying your records to reflect Change of Operator once you have received all necessary documentation from the companies involved, and perhaps in advance of our Notice of Concurrence/Approval of Change of Operator where Indian leases are involved.


We have no objection.

With further comment to Rulemaking, I wish to comment concerning the provision of Exhibits for upcoming Hearings. I would like to see the Uintah & Ouray Agency, BIA, and the Ute Indian Tribe, Energy & Mineral Resources Department added to the list of those parties that receive advance Exhibits so as to allow us to have research time prior to Hearing dates. We will be able to provide a more informed recommendation to the Oil, Gas and Mining Board. It would be best if we would receive only those Exhibits that concern Indian lands, specifically on or adjacent to Indian lands. This may be a difficult situation to attain, as it is not always clear where 'on or adjacent' occurs.

I am aware that you have gone to extra effort to correct this matter already, and I fully appreciate it. My request is intended only to allow the addition of Uintah & Ouray Agency and Ute Indian Tribe to the official listing.

We appreciate your concern, and hope that these comments are timely enough for consideration in the revision process.

CC: Minerals & Mining Section of RES
Ute Energy & Mineral Resources Department: Executive Director
chrono





United States Department of the Interior

BUREAU OF INDIAN AFFAIRS
Washington, D.C. 20240

FEB 10 2003

IN REPLY REFER TO:
Real Estate Services

Carroll A. Wilson
Principal Landman
Westport Oil and Gas Company, L.P.
1368 South 1200 East
Vernal, Utah 84078

Dear Mr. Wilson:

This is in response to your request for approval of RLI Insurance Company's Nationwide Oil and Gas Lease Bond No. RLB0005239 executed effective December 17, 2002, (\$150,000 coverage) with Westport Oil and Gas Company, L. P., as principal.

This bond is hereby approved as of the date of this correspondence and will be retained in the Bureau of Indian Affairs' Division of Real Estate Services, 1849 C Street, NW, MS-4512-MIB, Washington, D.C. 20240. All Bureau oil and gas regional offices and the surety are being informed of this action.

In cases where you have existing individual and/or collective bonds on file with one or more of our regional offices, you may now request those offices, directly, to terminate in lieu of coverage under this Nationwide Bond.

Enclosed is a copy of the approved bond for your files. If we may be of further assistance in this matter, please advise.

Sincerely,

Director, Office of Trust Responsibilities

ACTING

Enclosure



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155

IN REPLY REFER TO
UT-922

February 27, 2003

Westport Oil and Gas Company, L.P.
Attn: Gary D. Williamson
1670 Broadway, Suite 2800
Denver, Colorado 80202

Re: Natural Buttes Unit
Uintah County, Utah

Gentlemen:

On February 27, 2003, we received an indenture dated December 17, 2002, whereby El Paso Production Oil & Gas Company resigned as Unit Operator and Westport Oil and Gas Company, L.P., was designated as Successor Unit Operator for the Natural Buttes Unit, Uintah County, Utah.

This indenture was executed by all required parties and the signatory parties have complied with Sections 5 and 6 of the unit agreement. The instrument is hereby approved effective February 27, 2003. In approving this designation, the Authorized Officer neither warrants nor certifies that the designated party has obtained all required approval that would entitle it to conduct operations under the Natural Buttes Unit Agreement.

Your nationwide (Colorado) oil and gas bond No. 1203 will be used to cover all operations within the Natural Buttes Unit.

It is requested that you notify all interested parties of the change in unit operator. Copies of the approved instruments are being distributed to the appropriate federal offices, with one copy returned herewith.

Sincerely,

/s/ Robert A. Henricks

Robert A. Henricks
Chief, Branch of Fluid Minerals

Enclosure

bcc: Field Manager - Vernal (w/enclosure)
SITLA
Division of Oil, Gas & Mining
Minerals Adjudication Group
File - Natural Buttes Unit (w/enclosure)
Agr. Sec. Chron
Fluid Chron

UT922:TAThompson:tt:02/27/2003

RECEIVED

FEB 28 2003

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

5. LEASE DESIGNATION AND SERIAL NUMBER:

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:

8. WELL NAME and NUMBER:

Exhibit "A"

9. API NUMBER:

10. FIELD AND POOL, OR WILDCAT:

1. TYPE OF WELL

OIL WELL ☐

GAS WELL ☐

OTHER _____

2. NAME OF OPERATOR:

El Paso Production Oil & Gas Company

3. ADDRESS OF OPERATOR:

9 Greenway Plaza

CITY Houston

STATE TX

ZIP 77064-0995

PHONE NUMBER:

(832) 676-5933

4. LOCATION OF WELL

FOOTAGES AT SURFACE:

COUNTY:

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:

STATE:

UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Operator change to Westport Oil and Gas Company, L.P., 1670 Broadway, Suite 2800, Denver, CO. 80202-4800, effective December 17, 2002.

BOND # _____

State Surety Bond No. RLB0005236
Fee Bond No. RLB0005238

EL PASO PRODUCTION OIL & GAS COMPANY

By: _____

Jon R. Nelsen, Attorney-in-Fact

RECEIVED

FEB 28 2003

DIV. OF OIL, GAS & MINING

WESTPORT OIL AND GAS COMPANY, L.P.

NAME (PLEASE PRINT)

David R. Dix

TITLE

Agent and Attorney-in-Fact

SIGNATURE

DATE

12/17/02

(This space for State use only)

Form 3160-5
(August 1999)UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS

*Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.*FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

5. Lease Serial No.

SEE ATTACHED EXHIBIT "A"

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

WESTPORT OIL & GAS COMPANY, L.P.

3a. Address

P.O. BOX 1148 VERNAL, UT 84078

3b. Phone No. (include area code)

(435) 781-7023

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

8. Well Name and No.

SEE ATTACHED EXHIBIT "A"

9. API Well No.

SEE ATTACHED EXHIBIT "A"

10. Field and Pool, or Exploratory Area

11. County or Parish, State

UINTAH COUNTY, UT

SEE ATTACHED EXHIBIT "A"

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	SUCCESSOR OF
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	OPERATOR

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompletes horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zone following completion of the involved operations. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed when testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator determined that the site is ready for final inspection.

WESTPORT OIL & GAS COMPANY, L.P., IS CONSIDERED TO BE THE OPERATOR ON THE ATTACHED DESCRIBED LANDS AND IS RESPONSIBLE UNDER THE TERMS AND CONDITIONS OF THE LEASE FOR THE OPERATIONS CONDUCTED ON THE LEASED LANDS OR PORTIONS THEREOF. BOND COVERAGE FOR THIS WELL IS PROVIDED BY FEDERAL NATIONWIDE BOND NO. 158626364, EFFECTIVE FEBRUARY 1, 2002, AND BIA NATIONWIDE BOND NO. RLB0005239, EFFECTIVE FEBRUARY 10, 2003.

RECEIVED

MAR 04 2003

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

CHERYL CAMERON

Title

OPERATIONS

Date

March 4, 2003

DIV. OF OIL, GAS & MINING

Approved by

THIS SPACE FOR FEDERAL OR STATE USE

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)

OPERATOR CHANGE WORKSHEET

ROUTING

1. GLH

2. CDW ✓

3. FILE

X Change of Operator (Well Sold)

Designation of Agent/Operator

Operator Name Change

Merger

The operator of the well(s) listed below has changed, effective: **12-17-02****FROM: (Old Operator):**

EL PASO PRODUCTION OIL & GAS COMPANY

Address: 9 GREENWAY PLAZA

HOUSTON, TX 77064-0995

Phone: 1-(832)-676-5933

Account No. N1845

TO: (New Operator):

WESTPORT OIL & GAS COMPANY LP

Address: P O BOX 1148

VERNAL, UT 84078

Phone: 1-(435)-781-7023

Account No. N2115

CA No.

Unit: NATURAL BUTTES

WELL(S)

NAME	SEC TWN RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
NBU 18	26-10S-21E	43-047-30221	2900	FEDERAL	GW	S
NBU 22-27B	27-10S-21E	43-047-30360	2900	FEDERAL	GW	PA
NBU 33-27-10-21	27-10S-21E	43-047-30502	2900	FEDERAL	GW	PA
NBU 389	28-10S-21E	43-047-34229	2900	STATE	GW	P
NBU 359	29-10S-21E	43-047-33706	2900	STATE	GW	P
CIGE 2-29-10-21	29-10S-21E	43-047-30243	2900	STATE	GW	PA
NBU CIGE 85D-29-10-21	29-10S-21E	43-047-30855	2900	STATE	GW	PA
NBU 390	30-10S-21E	43-047-34230	2900	STATE	GW	P
NBU 67-30B	30-10S-21E	43-047-30574	2900	STATE	GW	PA
NBU CIGE 31-1-10-22	01-10S-22E	43-047-30511	2900	FEDERAL	GW	P
CIGE 105D-1-10-22	01-10S-22E	43-047-31758	2900	FEDERAL	GW	P
CIGE 194-1-10-22	01-10S-22E	43-047-32932	2900	FEDERAL	GW	P
CIGE 223-1-10-22	01-10S-22E	43-047-32983	2900	FEDERAL	GW	P
NBU 3-2B	02-10S-22E	43-047-30267	2900	STATE	GW	P
CIGE 67A-2-10-22P	02-10S-22E	43-047-30938	2900	STATE	GW	P
NBU 217-2	02-10S-22E	43-047-31282	2900	STATE	GW	P
CIGE 10-2-10-22	02-10S-22E	43-047-30425	2900	STATE	GW	P
CIGE 161-2-10-22	02-10S-22E	43-047-32168	2900	STATE	GW	P
CIGE 144-2-10-22	02-10S-22E	43-047-32022	2900	STATE	GW	P
CIGE 195-2-10-22	02-10S-22E	43-047-32797	2900	STATE	GW	P

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

1. (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 02/28/2003
2. (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 03/04/2003
3. The new company has been checked through the **Department of Commerce, Division of Corporations Database** on: 03/06/2003
4. Is the new operator registered in the State of Utah: YES Business Number: 1355743-0181
5. If **NO**, the operator was contacted on: _____

6. (R649-9-2) Waste Management Plan has been received on: IN PLACE

7. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM-12/31/2003 BIA-12/5/02

8. **Federal and Indian Units:**

The BLM or BIA has approved the successor of unit operator for wells listed on: 02/27/2003

9. **Federal and Indian Communization Agreements ("CA"):**

The BLM or BIA has approved the operator for all wells listed within a CA on: N/A

10. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: N/A

DATA ENTRY:

1. Changes entered in the **Oil and Gas Database** on: 03/21/2003
2. Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 03/21/2003
3. Bond information entered in RBDMS on: N/A
4. Fee wells attached to bond in RBDMS on: N/A

STATE WELL(S) BOND VERIFICATION:

1. State well(s) covered by Bond Number: RLB 0005236

FEDERAL WELL(S) BOND VERIFICATION:

1. Federal well(s) covered by Bond Number: 158626364

INDIAN WELL(S) BOND VERIFICATION:

1. Indian well(s) covered by Bond Number: RLB 0005239

FEE WELL(S) BOND VERIFICATION:

1. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number RLB 0005238
2. The **FORMER** operator has requested a release of liability from their bond on: N/A
The Division sent response by letter on: N/A

LEASE INTEREST OWNER NOTIFICATION:

3. (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: N/A

COMMENTS:

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENTFORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

WESTPORT OIL & GAS COMPANY, L.P.

3a. Address

P.O. BOX 1148 VERNAL, UT 84078

3b. Phone No. (include area code)

(435) 781-

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

Multiple Wells - see attached

5. Lease Serial No.

Multiple Wells - see attached

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

891008900A

8. Well Name and No.

Multiple Wells - see attached

9. API Well No.

Multiple Wells - see attached

10. Field and Pool, or Exploratory Area

Natural Buttes Unit

11. County or Parish, State

Uintah County, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☒ Notice of Intent☐ Subsequent Report☐ Final Abandonment Notice

TYPE OF ACTION

☐ Acidize☐ Alter Casing☐ Casing Repair☐ Change Plans☐ Convert to Injection☐ Deepen☐ Fracture Treat☐ New Construction☐ Plug and Abandon☐ Plug Back☐ Production (Start/Resume)☐ Reclamation☐ Recomplete☐ Temporarily Abandon☐ Water Disposal☐ Water Shut-Off☐ Well Integrity☐ Other _____

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

Westport Oil & Gas requests a variance to Onshore Order No. 4, Part IIIC.a. requiring each sales tank be equipped with a pressure-vacuum thief hatch and/or vent line valve. The variance is requested as an economic analysis shows the value of the shrunk condensate will not payout the incremental cost of purchasing and maintaining the valve resulting in a loss of value over the producing life of the well.

The volume lost to shrinkage by dropping the tank pressure from 6 ozs. to 0 psig is shown to be 0.3% of the tank volume. This was determined by lab analysis of a representative sample from the field. The sample shrunk from 98.82% of original volume to 98.52% when the pressure was dropped. The average NBU well produces approximately 6 bbls condensate per month. The resulting shrinkage would amount to 0.56 bbls per month lost volume due to shrinkage. The value of the shrunk and lost condensate does not recoup or payout the cost of installing and maintaining the valves and other devices that hold the positive tank pressure. An economic run based on the loss and costs is attached. Westport Oil & gas requests approval of this variance in order to increase the value of the well to the operator and the mineral royalty owners.

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

J.T. Conley

Signature

COPY SENT TO OPERATOR

Date:

Initials:

Title

Date

Operations Manager

9-2-2003

SEP 10 2003

DIV. OF OIL, GAS & MINING

Approved by

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title

Office

Date:

Accepted by the
Utah Division of
Oil, Gas and Mining

Date

Federal Approval of This
Action Is Necessary

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)

Westport Oil & Gas, L.P. Project Economics Worksheet

Instructions:

Fill in blue boxed areas with before and after project data. The evaluation results are shown below and graphed automatically at the bottom of the page. This sheet is protected to prevent accidental alteration of the formulas. See JTC for changes. OPX entered as annual costs and/or as unit OPX costs for \$/BF and \$/MCF

Project Name:

Condensate Shrinkage Economics

Is this job a well pull or production rig job ??? ☐ N (Y or N)

	BEFORE \$/Year	AFTER \$/Year	DIFFERENCE \$/Year
Gross Oil Revenue	\$1,088	\$1,099	\$11
Gross Gas Revenue	\$0	\$0	\$0
NGL Revenue	\$0	\$0	\$0
PULING UNIT SERVICE			\$0
WIRELINE SERVICE			\$0
SUBSURF EQUIP REPAIRS			\$0
COMPANY LABOR			\$0
CONTRACT LABOR	\$0	\$200	\$200
CONTR SERVICE			\$0
LEASE FUEL GAS	\$0	\$0	\$0
UTILITIES - ELECTRICITY	\$0	\$0	\$0
CHEMICAL TREATING			\$0
MATERIAL & SUPPLY	\$0	\$150	\$150
WATER & HAULING			\$0
ADMINISTRATIVE COSTS			\$0
GAS PLANT PROCESSING			\$0
Totals	\$0	\$350	\$350

Increased OPX Per Year

Investment Breakdown:

	Cap/Exp Code	Cost, \$
Capital \$	820/830/840	\$1,200
Expense \$	830/860	\$0
Total \$		\$1,200

Oil Price	\$ 23.00	\$/BO
Gas Price	\$ 3.10	\$/MCF
Electric Cost	\$ -	\$/ HP / day
OPX/BF	\$ 2.00	\$/BF
OPX/MCF	\$ 0.62	\$/MCF

Production & OPX Detail:

	Before		After		Difference
Oil Production	0.192	BOPD	0.194	BOPD	0.002
Gas Production	0	MCFPD	0	MCFPD	0
Wtr Production	0	BWPD	0	BWPD	0
Horse Power		HP		HP	0
Fuel Gas Burned		MCFPD		MCFPD	0

Project Life:

Life = 20.0 Years
(Life no longer than 20 years)

Internal Rate of Return:

After Tax IROR = #DIV/0!

AT Cum Cashflow:

Operating Cashflow = (\$2,917) (Discounted @ 10%)

Payout Calculation:

$$\text{Payout} = \frac{\text{Total Investment}}{\text{Sum(OPX + Incremental Revenue)}} = 1$$

Payout occurs when total AT cashflow equals investment
See graph below, note years when cashflow reaches zero

Payout = NEVER Years or #VALUE! Days


Gross Reserves:

Oil Reserves = 6 BO
Gas Reserves = 0 MCF
Gas Equiv Reserves = 38 MCFE

Notes/Assumptions:

An average N&U well produces 0.192 Bcpd with no tank pressure. The production is increased to 0.194 Bcpd if 6 ozs of pressure are placed on the tank. The increased production does not payout the valve cost or the estimated annual maintenance costs.

Project: Condensate Shrinkage Economics



Westport Oil and Gas, Inc.

NBU/Ouray Field

RFL 2003-022

COMPARISON OF FLASH BACK PRESSURES

Calculated by Characterized Equation-of-State

Flash Conditions		Gas/Oil Ratio (scf/STbbl) (A)	Specific Gravity of Flashed Gas (Air=1.000)	Separator Volume Factor (B)	Separator Volume Percent (C)
psig	°F				

Calculated at Laboratory Flash Conditions

80	70			1.019	
0	122	30.4	0.993	1.033	101.37%
0	60	0.0	—	1.000	98.14%

Calculated Flash with Backpressure using Tuned EOS

80	70			1.015	
6.0 oz	65	24.6	0.777	1.003	98.82%
0	60	0.0	—	1.000	98.52%
80	70			1.015	
4.0 oz	65	24.7	0.778	1.003	98.82%
0	60	0.0	—	1.000	98.52%
80	70			1.015	
2.0 oz	65	24.7	0.779	1.003	98.82%
0	60	0.0	—	1.000	98.52%
80	70			1.015	
0	65	24.8	0.780	1.003	98.82%
0	60	0.0	—	1.000	98.52%

(A) Cubic Feet of gas at 14.696 psia and 60 °F per Barrel of Stock Tank Oil at 60 °F.

(B) Barrels of oil at indicated pressure and temperature per Barrel of Stock Tank Oil at 60 °F.

(C) Oil volume at indicated pressure and temperature as a percentage of original saturated oil volume.

Note: Bubblepoint of sample in original sample container was 80 psig at 70° F with 1 cc water

WELL	LEGALS	STFLEASENO	CANUMBER	API NO
NBU 332	10-10-21 NWSW	UTU01416A	891008900A	430473364000S1
NBU 333	13-10-21 SWSW	ML23608	891008900A	430473364100S1 ✓
NBU 335	4-10-22 SENE	UTU01191	891008900A	430473372400S1
NBU 336	4-10-22 NWNE	U-01191	891008900A	430473402700S1
NBU 337	4-10-22 SENW	U-01191-A	891008900A	430473402000S1
NBU 338	5-10-22 NESE	UTU01191	891008900A	430473405800S1
NBU 339	5-10-22 NWSE	UTU01191	891008900A	430473440600S1
NBU 340	6-10-22 SWNE	UTU01195	891008900A	430473372500S1
NBU 340X	6-10-22 SWNE	UTU01195	891008900A	430473401500S1
NBU 341	6-10-22 SWNW	UTU464	891008900A	430473372600S1
NBU 342	7-10-22 NWSE	UTU468	891008900A	430473372700S1
NBU 343	8-10-22 NWNE	UTU01196C	891008900A	430473371900S1
NBU 344	8-10-22 SWNE	UTU01196C	891008900A	430473402100S1
NBU 345	10-10-22 SWNE	UTU02587	891008900A	430473370400S1 ✓
NBU 345-4E	4-10-21 SWSW	UTU01393B	891008900A	430473470000S1 ✓
NBU 347	11-10-22 NWSW	UTU01197A	891008900A	430473370900S1 ✓
NBU 348	11-10-22 SWSW	UTU01197A-ST	891008900A	430473400100S1
NBU 349	11-10-22 SWSE	UTU01197A-ST	891008900A	430473400200S1 ✓
NBU 350	14-10-22 NWNE	UTU01197A	891008900A	430473364200S1 ✓
NBU 351	30-10-22 SESE	UTU0132568A	891008900A	430473366800S1
NBU 352	9-9-21 SWNW	UTU0149767	891008900A	430473392200S1
NBU 353	27-9-21 SENW	U01194A	891008900A	430473320500S1 ✓
NBU 354	31-9-22 NENW	UTU464	891008900A	430473323100S1
NBU 356	30-9-22 NENW	U463	891008900A	430473323200S1
NBU 357	15-10-21 SWSW	UTU01791A	891008900A	430473372800S1
NBU 358	16-10-21 SESW	ML10755	891008900A	430473370800S1
NBU 359	29-10-21 NWNE	ML21330	891008900A	430473370600S1
NBU 360	29-10-22 SESW	UTU0145824	891008900A	430473377300S1
NBU 361	32-10-22 NWNW	ML22798	891008900A	430473370500S1 ✓
NBU 362	28-9-21 SESW	UTU0576	891008900A	430473377400S1
NBU 363	28-9-21 SESE	UTU0576	891008900A	430473377500S1
NBU 364	29-9-21 SESE	UTU0581	891008900A	430473377600S1
NBU 365	3-10-21 SESE	UTU0149078	891008900A	430473377700S1
NBU 366	10-10-21 NWNW	UTU0149079	891008900A	430473372900S1
NBU 367	11-10-22 NESW	UTU01197A-ST	891008900A	430473370700S1 ✓
NBU 370	17-9-21 NWSW	UTU0575	891008900A	430473467200S1 ✓
NBU 371	8-9-21 SWSE	UTU0575B	891008900A	430473467300S1 ✓
NBU 375	12-9-21 SWNE	UTU0141317	891008900A	430473444000S1 ✓
NBU 376	12-9-21 NENE	UTU0141317	891008900A	430473444100S1 ✓
NBU 377	31-9-21 NENW	UTU0582	891008900A	430473436300S1
NBU 378	31-9-21 NWNE	UTU0582	891008900A	430473436400S1
NBU 381	23-10-22 SESW	UTU01198B	891008900A	430473423400S1
NBU 382	22-10-22 SENW	U-01198-B	891008900A	430473423500S1
NBU 383	21-10-22 SESW	U-489	891008900A	430473423600S1

Division of Oil, Gas and Mining
OPERATOR CHANGE WORKSHEET

ROUTING

1. DJJ

2. CDW

X Change of Operator (Well Sold)

Operator Name Change/Merger

The operator of the well(s) listed below has changed, effective:

1/6/2006

FROM: (Old Operator):

N2115-Westport Oil & Gas Co., LP
 1368 South 1200 East
 Vernal, UT 84078

Phone: 1-(435) 781-7024

TO: (New Operator):

N2995-Kerr-McGee Oil & Gas Onshore, LP
 1368 South 1200 East
 Vernal, UT 84078

Phone: 1-(435) 781-7024

CA No.

Unit:

NATURAL BUTTES UNIT

WELL NAME

SEC TWN RNG

API NO

ENTITY

LEASE

WELL

WELL

NO

TYPE

TYPE

STATUS

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

1. (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 5/10/2006
2. (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 5/10/2006
3. The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 3/7/2006
- 4a. Is the new operator registered in the State of Utah: YES Business Number: 1355743-0181
- 4b. If **NO**, the operator was contacted on: _____
- 5a. (R649-9-2) Waste Management Plan has been received on: IN PLACE
- 5b. Inspections of LA PA state/fee well sites complete on: n/a 3 LA wells & all PA wells transferred
- 5c. Reports current for Production/Disposition & Sundries on: ok
6. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM 3/27/2006 BIA not yet
7. **Federal and Indian Units:**
 The BLM or BIA has approved the successor of unit operator for wells listed on: 3/27/2006
8. **Federal and Indian Communization Agreements ("CA"):**
 The BLM or BIA has approved the operator for all wells listed within a CA on: n/a
9. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: _____

DATA ENTRY:

1. Changes entered in the **Oil and Gas Database** on: 5/15/2006
2. Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 5/15/2006
3. Bond information entered in RBDMS on: 5/15/2006
4. Fee/State wells attached to bond in RBDMS on: 5/16/2006
5. Injection Projects to new operator in RBDMS on: _____
6. Receipt of Acceptance of Drilling Procedures for APD/New on: n/a Name Change Only

BOND VERIFICATION:

1. Federal well(s) covered by Bond Number: CO1203
2. Indian well(s) covered by Bond Number: RLB0005239
3. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number RLB0005236
- a. The **FORMER** operator has requested a release of liability from their bond on: n/a rider added KMG
- The Division sent response by letter on: _____

LEASE INTEREST OWNER NOTIFICATION:

4. (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: 5/16/2006

COMMENTS:

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

5. Lease Serial No.

MULTIPLE LEASES

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

MUTIPLE WELLS

9. API Well No.

10. Field and Pool, or Exploratory Area

11. County or Parish, State

UINTAH COUNTY, UTAH

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

KERR-McGEE OIL & GAS ONSHORE LP

3a. Address

1368 SOUTH 1200 EAST VERNAL, UT 84078

3b. Phone No. (include area code)

(435) 781-7024

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SEE ATTACHED

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other CHANGE OF OPERATOR
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

PLEASE BE ADVISED THAT KERR-McGEE OIL & GAS ONSHORE LP, IS CONSIDERED TO BE THE OPERATOR OF THE ATTACHED WELL LOCATIONS. EFFECTIVE JANUARY 6, 2006. KERR-McGEE OIL & GAS ONSHORE LP, IS RESPONSIBLE UNDER TERMS AND CONDITIONS OF THE LEASE(S) FOR THE OPERATIONS CONDUCTED UPON LEASE LANDS. BOND COVERAGE IS PROVIDED BY STATE OF UTAH NATIONWIDE BOND NO. RLB0005237.

RECEIVED

MAY 10 2006

DIV. OF OIL, GAS & MINING

BLM BOND = C01203
BIA BOND = RLB0005239

APPROVED 5/16/06

Earlene Russell
Division of Oil, Gas and Mining
Earlene Russell, Engineering Technician

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

RANDY BAYNE

Title

DRILLING MANAGER

Signature

Date

May 9, 2006

THIS SPACE FOR FEDERAL OR STATE USE

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

5. Lease Serial No.

MULTIPLE LEASES

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

MUTIPLE WELLS

9. API Well No.

10. Field and Pool, or Exploratory Area

11. County or Parish, State

UINTAH COUNTY, UTAH

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

WESTPORT OIL & GAS COMPANY L.P.

3a. Address

1368 SOUTH 1200 EAST VERNAL, UT 84078

3b. Phone No. (include area code)

(435) 781-7024

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SEE ATTACHED

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other CHANGE OF OPERATOR
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

EFFECTIVE JANUARY 6, 2006, WESTPORT OIL & GAS COMPANY L.P., HAS RELINQUISHED THE OPERATORSHIP OF THE ATTACHED WELL LOCATIONS TO KERR-McGEE OIL & GAS ONSHORE LP.

APPROVED 5/16/06
Earlene Russell
Division of Oil, Gas and Mining
Earlene Russell, Engineering Technician

RECEIVED
MAY 10 2006

DIV OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

BRAD LANEY

Title

ENGINEERING SPECIALIST

Signature

Date

May 9, 2006

THIS SPACE FOR FEDERAL OR STATE USE

Approved by

Brad Laney

Title

Date

5-9-06

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-21330
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: NBU 359
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1220 FNL 2035 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNE Section: 29 Township: 10.0S Range: 21.0E Meridian: S		9. API NUMBER: 43047337060000
PHONE NUMBER: 720 929-6007 Ext		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
COUNTY: UTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 6/24/2010	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input checked="" type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> ALTER CASING	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> OTHER:	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. THIS WELL RETURNED TO PRODUCTION ON 6/24/2010.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY June 28, 2010		
NAME (PLEASE PRINT) Andy Lytle	PHONE NUMBER 720 929-6100	TITLE Regulatory Analyst
SIGNATURE N/A	DATE 6/24/2010	

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9			
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-21330			
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:			
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES			
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: NBU 359			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1220 FNL 2035 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNE Section: 29 Township: 10.0S Range: 21.0E Meridian: S		9. API NUMBER: 43047337060000			
PHONE NUMBER: 720 929-6515 Ext		9. FIELD and POOL or WILDCAT: NATURAL BUTTES			
COUNTY: UINTAH		STATE: UTAH			
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA					
TYPE OF SUBMISSION	TYPE OF ACTION				
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 9/28/2011 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input checked="" type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/> </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input checked="" type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input checked="" type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>			
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. The operator requests authorization to plug and abandon the subject well location. Attached to this sundry is the plug and abandonment procedure. Thank you.					
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY					
NAME (PLEASE PRINT) Jaime Scharnowske	PHONE NUMBER 720 929-6304	TITLE Regulatory Analyst			
SIGNATURE N/A	DATE 9/28/2011				

NBU 359
1220' FNL & 2035' FEL
NWNE33706 SEC.29, T10S, R21E
Uintah County, UT

KBE: 5225' API NUMBER: 4304733706
GLE: 5210'* LEASE NUMBER: ML-21330
** Not consistent with Completion Report, but is consistent with log data and field data.
TD: 6847'
PBTD: 6808'

CASING : 12 1/4" hole
8.625" 32# K55 @ 267' KB

7.875" hole
4.5" 11.6# K-55 @ 6846'
TOC @ ~470' per CBL

PERFORATIONS: Wasatch 5078' - 6699'

Tubular/Borehole	Drift inches	Collapse psi	Burst psi	Capacities		
				Gal./ft.	Cuft/ft.	Bbl./ft.
2.375" 4.7# J-55 tbg.	1.901	8100	7700	0.1624	0.02171	0.00387
4.5" 11.6# J/K-55	3.875	4960	5350	0.6528	0.0872	0.0155
8.625" 32# J-55	7.796	2530	3930	2.5599	0.3422	0.0609
Annular Capacities						
2.3/8" tbg. X 4 1/2" csg				0.4226	0.0565	0.01
4.5" csg X 8 5/8" 32# csg				1.7346	0.2318	0.0413
4.5" csg X 7.7/8 borehole				1.704	0.2278	0.0406
8.5/8" csg X 12 1/4" borehole				3.0874	0.4127	0.0735

GEOLOGIC INFORMATION:

Formation	Depth to top, ft.
Uinta	Surface
Green River	1065'
Bird's Nest	1270'
Mahogany	1680'
Base of Parachute	2544'
Wasatch	4222'

Tech. Pub. #92 Base of USDW's

USDW Elevation	~900' MSL
USDW Depth	~4325' KBE

NBU 359 PLUG & ABANDONMENT PROCEDURE**GENERAL**

- H₂S MAY BE PRESENT. CHECK FOR H₂S AND TAKE APPROPRIATE PRECAUTIONS.
- CEMENT QUANTITIES BELOW ASSUME NEAT CLASS G, YIELD 1.145 CUFT./SX. IF A DIFFERENT PRODUCT IS USED, WELLSITE PERSONNEL ARE RESPONSIBLE FOR CORRECTING QUANTITIES TO YIELD THE STATED SLURRY VOLUME. WHEN SQUEEZING, INCLUDE 10% EXCESS PER 1000' OF DEPTH.
- TREATED FRESH WATER WILL BE PLACED BETWEEN ALL PLUGS INSTEAD OF BRINE.
- ALL DISPLACEMENT FLUID SHALL CONTAIN CORROSION INHIBITOR AND BIOCIDES. PREMIX 5 GALLONS PER 100 BBLs FLUID.
- PLUGS ARE TO BE TAGGED TO ENSURE THEY ARE AT DEPTH SPECIFIED.
- NOTIFY UDOGM 24 HOURS BEFORE MOVING ON LOCATION.

PROCEDURE

Note: An estimated 184 sx Class "G" cement needed for procedure

Note: Gyro has not been run on this well.

1. MIRU. KILL WELL AS NEEDED. ND WH, NU AND TEST BOPE.
2. **PLUG #1, ISOLATE WASATCH PERFORATIONS (5078' - 6699')**: RIH W/ 4 ½" CIBP. SET @ ~5030'. RELEASE CIBP, PUH 10', BRK CIRC W/ FRESH WATER. RELEASE CIBP, PUH 10', BRK CIRC W/ FRESH WATER. DISPLACE A MINIMUM OF **8 SX / 1.6 BBL / 8.70 CUFT**. ON TOP OF PLUG. PUH ABOVE TOC (~4930'). REVERSE CIRCULATE W/ TREATED WATER.
3. **PLUG #2, PROTECT TOP OF WASATCH (4222') & BASE OF USDW (~4325')**: PUH TO ~4430'. BRK CIRC W/ FRESH WATER. DISPLACE **24 SX / 4.8 BBL / 27.0 CUFT** AND BALANCE PLUG W/ TOC @ ~4120' (310' COVERAGE). PUH ABOVE TOC. REVERSE CIRCULATE W/ TREATED WATER.
4. **PLUG #3, PROTECT BASE OF PARACHUTE MEMBER (~2544')**: PUH TO ~2650'. BRK CIRC W/ FRESH WATER. DISPLACE **16 SX / 3.3 BBL / 18.3 CUFT** AND BALANCE PLUG W/ TOC @ ~2440' (210' COVERAGE). PUH ABOVE TOC. REVERSE CIRCULATE W/ TREATED WATER.
5. **PLUG #4, PROTECT TOP OF MAHOGANY (1680')**: PUH TO ~1780'. BRK CIRC W/ FRESH WATER. DISPLACE **16 SX / 3.1 BBL / 17.4 CUFT** AND BALANCE PLUG W/ TOC @ ~1580' (200' COVERAGE). PUH ABOVE TOC. REVERSE CIRCULATE W/ TREATED WATER.
6. **PLUG #5, PROTECT TOP OF BIRD'S NEST (~1270') & TOP OF GREEN RIVER (1065')**: PUH TO ~1370'. BRK CIRC W/ FRESH WATER. DISPLACE **31 SX / 6.4 BBL / 35.8 CUFT** AND BALANCE PLUG W/ TOC @ ~960' (410' COVERAGE). PUH ABOVE TOC. REVERSE CIRCULATE W/ TREATED WATER.
7. **PLUG #6, SURFACE HOLE**: POOH. RIH W/ WIRELINE, PERFORATE @ 320' W/ 4 SPF. POOH W/ WIRELINE. RU CEMENT SERVICE TO PROD CSG. PUMP **89 SX / 18.1 BBL / 101.9 CUFT** OR SUFFICIENT VOLUME TO FILL ANNULUS AND CASING TO SURFACE.
8. CUT OFF WELLHEAD AND INSTALL MARKER PER BLM GUIDELINES.
9. RDMO. TURN OVER TO OPERATIONS FOR SURFACE REHAB. SURFACE RECLAMATION TO BE PERFORMED IN ACCORDANCE WITH R649-3-34 - WELL SITE RESTORATION.

ALM 9/8/11




APC 206 2/01

PROJECT COMPUTATIONS

NO. _____ OF _____ SHEETS

DATE Nov 3 59 PROJECT _____ JOB NO. _____

BY _____ CHK.: _____ SUBJECT _____



STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9																														
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-21330																														
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:																														
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES																														
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: NBU 359																														
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1220 FNL 2035 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNE Section: 29 Township: 10.0S Range: 21.0E Meridian: S		9. API NUMBER: 43047337060000																														
9. FIELD and POOL or WILDCAT: NATURAL BUTTES		COUNTY: UTAH																														
STATE: UTAH																																
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA																																
TYPE OF SUBMISSION <input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 9/28/2011 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	TYPE OF ACTION <table style="width: 100%; border: none;"> <tr> <td><input type="checkbox"/> ACIDIZE</td> <td><input type="checkbox"/> ALTER CASING</td> <td><input type="checkbox"/> CASING REPAIR</td> </tr> <tr> <td><input type="checkbox"/> CHANGE TO PREVIOUS PLANS</td> <td><input type="checkbox"/> CHANGE TUBING</td> <td><input type="checkbox"/> CHANGE WELL NAME</td> </tr> <tr> <td><input type="checkbox"/> CHANGE WELL STATUS</td> <td><input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS</td> <td><input type="checkbox"/> CONVERT WELL TYPE</td> </tr> <tr> <td><input type="checkbox"/> DEEPEN</td> <td><input type="checkbox"/> FRACTURE TREAT</td> <td><input type="checkbox"/> NEW CONSTRUCTION</td> </tr> <tr> <td><input type="checkbox"/> OPERATOR CHANGE</td> <td><input checked="" type="checkbox"/> PLUG AND ABANDON</td> <td><input type="checkbox"/> PLUG BACK</td> </tr> <tr> <td><input type="checkbox"/> PRODUCTION START OR RESUME</td> <td><input type="checkbox"/> RECLAMATION OF WELL SITE</td> <td><input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION</td> </tr> <tr> <td><input type="checkbox"/> REPERFORATE CURRENT FORMATION</td> <td><input type="checkbox"/> SIDETRACK TO REPAIR WELL</td> <td><input type="checkbox"/> TEMPORARY ABANDON</td> </tr> <tr> <td><input type="checkbox"/> TUBING REPAIR</td> <td><input type="checkbox"/> VENT OR FLARE</td> <td><input type="checkbox"/> WATER DISPOSAL</td> </tr> <tr> <td><input type="checkbox"/> WATER SHUTOFF</td> <td><input type="checkbox"/> SI TA STATUS EXTENSION</td> <td><input type="checkbox"/> APD EXTENSION</td> </tr> <tr> <td><input type="checkbox"/> WILDCAT WELL DETERMINATION</td> <td><input type="checkbox"/> OTHER</td> <td>OTHER: <input style="width: 100px;" type="text"/></td> </tr> </table>		<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> OPERATOR CHANGE	<input checked="" type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: <input style="width: 100px;" type="text"/>
<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR																														
<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME																														
<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE																														
<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION																														
<input type="checkbox"/> OPERATOR CHANGE	<input checked="" type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK																														
<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION																														
<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON																														
<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL																														
<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION																														
<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: <input style="width: 100px;" type="text"/>																														
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. The operator requests authorization to plug and abandon the subject well location. Attached to this sundry is the plug and abandonment procedure. Thank you. <div style="display: flex; justify-content: space-between;"> <div style="width: 45%;"> <p style="text-align: center; font-weight: bold;">APPROVED BY THE STATE OF UTAH DIVISION OF OIL, GAS, AND MINING</p> <p>DATE: <u>5/9/2012</u></p> <p>BY: <u>[Signature]</u></p> <p>* * See Conditions of Approval (Attached)</p> </div> <div style="width: 45%; text-align: center;"> <p>Accepted by the Utah Division of Oil, Gas and Mining</p> <p style="font-size: 1.2em; font-weight: bold;">FOR RECORD ONLY</p> <p style="font-size: 1.2em; font-weight: bold;">RECEIVED</p> <p style="font-size: 1.2em; font-weight: bold;">* SEP 28 2011</p> <p style="font-size: 0.8em;">DIV. OF OIL, GAS & MINING</p> <p style="font-size: 0.8em;">* Verified by operator of Docu Processing error of original Submittal on May 9, 2012 - properly processed at that time [Signature]</p> </div> </div>																																
NAME (PLEASE PRINT) Jaime Scharnowske	PHONE NUMBER 720 929-6304	TITLE Regulatory Analyst																														
SIGNATURE N/A		DATE 9/28/2011																														

NBU 359
 1220' FNL & 2035' FEL
 NWNE33706 SEC.29, T10S, R21E
 Uintah County, UT

KBE: 5225' API NUMBER: 4304733706
 GLE: 5210'* LEASE NUMBER: ML-21330
 ** Not consistent with Completion Report, but is consistent with log data and field data.
 TD: 6847'
 PBTD: 6808'

CASING : 12 1/4" hole
 8.625" 32# K55 @ 267' KB

 7.875" hole
 4.5" 11.6# K-55 @ 6846'
 TOC @ ~470' per CBL

PERFORATIONS: Wasatch 5078' - 6699'

Tubular/Borehole	Drift inches	Collapse psi	Burst psi	Capacities		
				Gal./ft.	Cuft./ft.	Bbl./ft.
2.375" 4.7# J-55 tbg.	1.901	8100	7700	0.1624	0.02171	0.00387
4.5" 11.6# J/K-55	3.875	4960	5350	0.6528	0.0872	0.0155
8.625" 32# J-55	7.796	2530	3930	2.5599	0.3422	0.0609
Annular Capacities						
2.3/8" tbg. X 4 1/2" csg				0.4226	0.0565	0.01
4.5" csg X 8 5/8" 32# csg				1.7346	0.2318	0.0413
4.5" csg X 7.7/8 borehole				1.704	0.2278	0.0406
8.5/8" csg X 12 1/4" borehole				3.0874	0.4127	0.0735

GEOLOGIC INFORMATION:

Formation	Depth to top, ft.
Uinta	Surface
Green River	1065'
Bird's Nest	1270'
Mahogany	1680'
Base of Parachute	2544'
Wasatch	4222'

Tech. Pub. #92 Base of USDW's
 USDW Elevation ~900' MSL
 USDW Depth ~4325' KBE

NBU 359 PLUG & ABANDONMENT PROCEDURE

GENERAL

- H₂S MAY BE PRESENT. CHECK FOR H₂S AND TAKE APPROPRIATE PRECAUTIONS.
- CEMENT QUANTITIES BELOW ASSUME NEAT CLASS G, YIELD 1.145 CUFT./SX. IF A DIFFERENT PRODUCT IS USED, WELLSITE PERSONNEL ARE RESPONSIBLE FOR CORRECTING QUANTITIES TO YIELD THE STATED SLURRY VOLUME. WHEN SQUEEZING, INCLUDE 10% EXCESS PER 1000' OF DEPTH.
- TREATED FRESH WATER WILL BE PLACED BETWEEN ALL PLUGS INSTEAD OF BRINE.
- ALL DISPLACEMENT FLUID SHALL CONTAIN CORROSION INHIBITOR AND BIOCIDES. PREMIX 5 GALLONS PER 100 BBLs FLUID.
- PLUGS ARE TO BE TAGGED TO ENSURE THEY ARE AT DEPTH SPECIFIED.
- NOTIFY UDOGM 24 HOURS BEFORE MOVING ON LOCATION.

PROCEDURE

Note: An estimated 184 sx Class "G" cement needed for procedure

Note: Gyro has not been run on this well.

1. MIRU. KILL WELL AS NEEDED. ND WH, NU AND TEST BOPE.
2. **PLUG #1, ISOLATE WASATCH PERFORATIONS (5078' - 6699')**: RIH W/ 4 ½" CIBP. SET @ ~5030'. RELEASE CIBP, PUH 10', BRK CIRC W/ FRESH WATER. RELEASE CIBP, PUH 10', BRK CIRC W/ FRESH WATER. DISPLACE A MINIMUM OF 8 SX / 1.6 BBL / 8.70 CUFT. ON TOP OF PLUG. PUH ABOVE TOC (~4930'). REVERSE CIRCULATE W/ TREATED WATER.
3. **PLUG #2, PROTECT TOP OF WASATCH (4222') & BASE OF USDW (~4325')**: PUH TO ~4430'. BRK CIRC W/ FRESH WATER. DISPLACE 24 SX / 4.8 BBL / 27.0 CUFT AND BALANCE PLUG W/ TOC @ ~4120' (310' COVERAGE). PUH ABOVE TOC. REVERSE CIRCULATE W/ TREATED WATER.
4. **PLUG #3, PROTECT BASE OF PARACHUTE MEMBER (~2544')**: PUH TO ~2650'. BRK CIRC W/ FRESH WATER. DISPLACE 16 SX / 3.3 BBL / 18.3 CUFT AND BALANCE PLUG W/ TOC @ ~2440' (210' COVERAGE). PUH ABOVE TOC. REVERSE CIRCULATE W/ TREATED WATER.
5. **PLUG #4, PROTECT TOP OF MAHOGANY (1680')**: PUH TO ~1780'. BRK CIRC W/ FRESH WATER. DISPLACE 16 SX / 3.1 BBL / 17.4 CUFT AND BALANCE PLUG W/ TOC @ ~1580' (200' COVERAGE). PUH ABOVE TOC. REVERSE CIRCULATE W/ TREATED WATER.
6. **PLUG #5, PROTECT TOP OF BIRD'S NEST (~1270') & TOP OF GREEN RIVER (1065')**: PUH TO ~1370'. BRK CIRC W/ FRESH WATER. DISPLACE 31 SX / 6.4 BBL / 35.8 CUFT AND BALANCE PLUG W/ TOC @ ~960' (410' COVERAGE). PUH ABOVE TOC. REVERSE CIRCULATE W/ TREATED WATER.
7. **PLUG #6, SURFACE HOLE: POOH. RIH W/ WIRELINE, PERFORATE @ 320' W/ 4 SPF. POOH W/ WIRELINE. RU CEMENT SERVICE TO PROD CSG. PUMP 89 SX / 18.1 BBL / 101.9 CUFT OR SUFFICIENT VOLUME TO FILL ANNULUS AND CASING TO SURFACE.**
8. CUT OFF WELLHEAD AND INSTALL MARKER PER BLM GUIDELINES.
9. RDMO. TURN OVER TO OPERATIONS FOR SURFACE REHAB. SURFACE RECLAMATION TO BE PERFORMED IN ACCORDANCE WITH R649-3-34 - WELL SITE RESTORATION.

PROJECT COMPUTATIONS

NO. _____ OF _____ SHEETS

DATE Mar 359


PROJECT _____

JOB NO. _____

BY _____

CHK.: _____

SUBJECT _____





GARY R. HERBERT
Governor

GREGORY S. BELL
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

CONDITIONS OF APPROVAL TO PLUG AND ABANDON WELL

Well Name and Number: NBU 359
API Number: 43-047-33706
Operator: Kerr-McGee Oil & Gas Onshore, L.P.
Reference Document: Original Sundry Notice dated September 28, 2011,
received by DOGM on September 28, 2011- reprocessed
on May 9, 2012 because of original
filing processing error.

Approval Conditions:

1. Notify the Division at least 24 hours prior to conducting abandonment operations. Please call Dan Jarvis at 801-538-5338.
2. All balanced plugs shall be tagged to ensure they remain at the depth specified by the proposal.
3. All annuli shall be cemented from a minimum depth of 100' to the surface.
4. Surface reclamation shall be done in accordance with R649-3-34 – Well Site Restoration.
5. All requirements in the Oil and Gas Conservation General Rule R649-3-24 shall apply.
6. If there are any changes to the plugging procedure or the wellbore configuration, notify Dustin Doucet at 801-538-5281 (ofc) or 801-733-0983 (home) prior to continuing with the procedure.
7. All other requirements for notice and reporting in the Oil and Gas Conservation General Rules shall apply.

Dustin K. Doucet
Petroleum Engineer

May 9, 2012

Date



Wellbore Diagram

API Well No: 43-047-33706-00-00

Permit No:

Well Name/No: NBU 359

Company Name: KERR-MCGEE OIL & GAS ONSHORE, L.P.

Location: Sec: 29 T: 10S R: 21E Spot: NWNE

Coordinates: X: 621924 Y: 4420118

Field Name: NATURAL BUTTES

County Name: UINTAH

String Information

String	Bottom (ft sub)	Diameter (inches)	Weight (lb/ft)	Length (ft)
HOL1	252	12.25		
SURF	252	8.625	32	252
HOL2	6846	7.875		
PROD	6846	4.5	11.6	6846
T1	6675	2.375		

Capacity
(5/CF)

11.459

7 7/8" x 4 1/2" (108)

3.347

8 7/8" x 4 1/2"

4.315

Cement from 252 ft. to surface

Surface: 8.625 in. @ 252 ft.

Hole: 12.25 in. @ 252 ft.

Plug # 6

$$\begin{aligned} \text{hole } 68' / (1.15) (3.347) &= 185X \\ 8 7/8" 252' / (1.15) (4.315) &= 515X \\ 320' / (1.15) (11.459) &= 245X \end{aligned}$$

935X total propose 895X OK.

Plug # 5

$$(315X)(1.15)(11.459) = 408'$$

TOC @ 962' OK.

Plug # 4

$$165X = 210'$$

TOC @ 1570' OK.

Plug # 3

$$(165X)(1.15)(11.459) = 210'$$

TOC @ 2440' OK.

Cement Information

String	BOC (ft sub)	TOC (ft sub)	Class	Sacks
PROD	6846	470	PC	1245
PROD	6846	470	LT	660
SURF	252	0	PM	150

Perforation Information

Top (ft sub)	Bottom (ft sub)	Shts/Ft	No Shts	Dt Squeeze
5078	6699			

Plug # 2

$$(245X)(1.15)(11.459) = 316'$$

TOC @ 4114' OK.

Plug # 1

$$(85X)(1.15)(11.459) = 105'$$

TOC @ 4925' OK.

Formation Information

Formation	Depth
UNTA	0
GRRV	1065
MHGBN	1680
PARCK	2544
BMSW	4100
WSTC	4222

Cement from 6846 ft. to 470 ft.

Tubing: 2.375 in. @ 6675 ft.

Production: 4.5 in. @ 6846 ft.

Hole: 7.875 in. @ 6846 ft.

Hole: Unknown

TD: 6847 TVD: PBTD: 6808

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-21330
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: NBU 359
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1220 FNL 2035 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNE Section: 29 Township: 10.0S Range: 21.0E Meridian: S		9. API NUMBER: 43047337060000
PHONE NUMBER: 720 929-6514		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 5/14/2012	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input checked="" type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION	
<input type="checkbox"/> DRILLING REPORT Report Date:	OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. The operator has concluded the plug and abandonment operations on the subject well location on 05/14/2012. Please see the attached chronological well history for details and updated latitude and longitude locations.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY July 25, 2012		
NAME (PLEASE PRINT) Cara Mahler	PHONE NUMBER 720 929-6029	TITLE Regulatory Analyst I
SIGNATURE N/A	DATE 7/24/2012	

US ROCKIES REGION
Operation Summary Report

Well: NBU 359

Spud Date: 12/29/2000

Project: UTAH-UINTAH

Site: NBU 359

Rig Name No: WESTERN WELLSITE/UNK

Event: ABANDONMENT

Start Date: 5/10/2012

End Date: 5/14/2012

Active Datum: RKB @0.00usft (above Mean Sea Level)

UWI: NBU 359

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
5/10/2012	7:00 - 17:00	10.00	ABANDP					PREJOB SAFETY MEETING, MIRU, BLOW DOWN WELL, KILL WELL WITH 50BLS TMAC, NDWH, NUBOP, RU PRS, TOH AND TEST TUBING, RU WIRELINE, RIH WITH GAUGE RING TO 5050', POOH WITH SAME, RIH WITH CIBP AND SET AT 5030', POOH WITH WIRELINE, RIH WITH GYRO SURVEY, POOH WITH SAME, RD WIRELINE, SIW, SDFN
5/11/2012	7:00 - 17:00	10.00	ABANDP					PREJOB SAFETY MEETING, MIRU, TIH AND TAG CIBP AT 5030', PUH TO 5020', LOAD HOLE WITH 75BLS TMAC, PRESSURE TEST CASING TO 500PSI HELD, MIX AND PUMP 10SXS CLASS G CEMENT, TOH TO 4445', MIX AND PUMP 25SXS CLASS G CEMENT, TOH TO 2660', MIX AND PUMP 20SXS CLASS G CEMENT, TOH TO 1784', MIX AND UMP 20SXS CLASS G CEMENT, TOH TO 1395', MIX AND PUMP 35SXS CLASS G CEMENT, TOH, SIW, SDFN
5/14/2012	7:00 - 17:00	10.00	ABANDP					PREJOB SAFETY MEETING, RU WIRELINE, SHOOT PERFS AT 320', ATTEMPT TO GET RATE INTO PERFS FAILED, RD WIRELINE, NDBOP, TIH TO 370', MIX AND PUMP 30SXS CLASS G CEMENT TO SURFACE, TOH, RD, DIG OUT WELLHEAD, CUT OFF WELLHEAD, 1" DOWN SURFACE ANNULUS 105', MIX AND PUMP 35SXS CLASS G CEMENT TO SURFACE, WELD ON INFO PLATE, BACKFILL, CLEAN LOCATION, SDFN
LAT/LONG: 39.92242/-109.57265								